F IX 4

Previous References

1946 47
(Incl)

File No 38-46
Serial Nos 118, 119

Mysore Lake Act & Accumulation control Act No XXX of 1957

Later References

178 Dep 440/53

GTB 68-54-1, 2

GENERAL AND REVENUE SECRETARIAT

GTB 59 55 4

YCM 58 9856

Serial Nos

TRO

Part B for May 47

SUBJECT

Estimate for Rs 79,100 for draining off Doddakere tank in Mysore City as an Antimalaria measure

K 16393-98 Dt 26.5.47

To

The Chairman C & T B & D Mysore
The Engr for R & B.
The Engr — Irrigation
President City Mil Cl
Director of P H Mysore
Comptroller to Gov

Sanction Ro

App F IX—4

Previous References

(195)

File No

Serial Nos

Later References

MYSORE GOVERNMENT SECRETARIAT

Serial Nos

Part B for

SUBJECT

WD 0249—GPB—25 000—16 9 55

C 1890

DEWAN'S OFFICE
NO Vasantha Mahal, Mysore
M 580/1

667

1st November 1941

P W SECRETARIAT
M 56/1
Date 4/11/41

My dear Madhava Rau,

With reference to our conversation of this morning, I send you herewith the note you asked for on the subject of the treatment of the tanks in and around the Mysore City for anti-malaria purposes

A feature that is peculiar to these tanks is that they are supplied by long contour channels which serve to catch the water running off the hills and the high ground and lead it into them Some of the tanks have no atchkat Some of the bunds are leaky, and the result is the creation of swamps by seepage What I ventured to suggest was that, instead of dealing with the tanks and the swamps above and below them piecemeal, it would be better to deal with the whole case in a comprehensive manner with the aid of contour maps of the whole area If the tanks have no atchkat, there is obviously no purpose in retaining the contour channels On the other hand, if there are suitable ways of drawing the water from these channels in such a fashion that it will not create swamps, then it would be preferable to do this It may be added that in several cases the contour channels themselves, having been neglected for some years, present a chain of pools of stagnant water

In some cases it would seem to be feasible to use the water profitably for growing ~~food~~ fodder crops on the lands on which swamps are created, for instance, the area between the Chamappaji Urs Road and the Goblikere It seems desirable to consider whether the small atchkat of the Goblikere presented by the Krishnagara Gardens should not be acquired The whole of the water could then be passed out through the northern end of the tank into the big drain through the Doddakere

As regards the Doddakere itself, it seems to a lay-man to be a cumbrous plan to allow a great quantity of the water to come in at the north-west corner, causing a flooding of the tank whenever there is heavy rain with subsequent large numbers of small pools, instead of diverting the flood water straight down the valley which runs in a southerly direction from the Palace to the Sewage Farm A great part of this area is in a terrible condition

Lower down I would venture to suggest that a vigorous attempt be made to deal with the question of the treatment of sewage water, (I understand that no action has yet been taken on the report of the Committee which sat some years ago) and to extend the area under cultivation both under the Sewage Farm and under the Dalvoy Tank The Dalvoy Tank is getting more and more foul every year through being kept constantly filled with sewage water, and the <u>halla</u> which runs from it to Kadakola is rendered foul with sewage the whole way, while a properly thought-out scheme might provide an extremely valuable cultivated area

Yours sincerely,

G D Schmulen

SNK

(3

Bangalore,

3rd November 1941

My dear Sir Charles,

I am much obliged for your D O letter No C 1890 of the 1st November communicating your suggestions in regard to the treatment of the tanks in and around Mysore City for anti-malaria purposes I shall, of course, have these suggestions examined

Yours sincerely,

(sd) N MADHAVA RAU

Sir Charles Todhunter, K C S I ,
Private Secretary to His Highness
the Maharaja of Mysore,
MYSORE

	Serial No	
		Correspondence ending with letter No 16698 dated 11 3 42 from the Chief Engineer of Mysore Re Treatment of tanks in and around Mysore city for anti Malaria purposes
S		1 Kind reference is requested to Sir Charles Todhunter's letter No C 1890 dt 1 11 41 to the address of the Dewan re the treatment of tanks for anti-malaria purposes around the Mysore city, which was received in this secn for obtaining a report from the Ch. Engineer
B		2 A report was called for from the Chief Engineer in T O letter No 27 54/S dt 7 11 41 on the subject, and reminders were also issued
E		subsequently. It is now reported that replies from the Superintending Engineer and the Director of Public Health are still awaited
		3 It is nearly 5 months since the report was called for and it is for consideration whether a time-limit maybe fixed for the Ch Engineers report.
		4 1) Yes a fortnight
		2) Copies to Supt Engr & Dr of P H for info
		Ch 19/3/42
		5 Subd with a dft for approval

NOTE—Cont Sheet

WD —G1 B—5 000—23 10 41

19/3

19/3

Issue

23/3/42

(Issued in MR 47425 27 dated 25/3/1942)

Treatment of tanks in and around Mysore city for anti-Malaria purposes

File No. of 194

General and Revenue Secretariat

Serial No

Letter No 17489 dated 25.3.42 from the Chief Engineer of Mysore forwards a copy of report of the Asst Engineer, Head Quarter Range, Mysore, on the above subject.

Submitted for perusal

Final proposals in the matter and the estimate for the work in consultation with the Director of Public Health will be called for, if approved,

If the Chief Engineer has merely submitted the report of the Asst Engineer, Head Quarters Range which contains certain proposals for treatment of tanks in and around Mysore City as an anti-malarial measure this is an important subject and let Sri who is in Mysore should have paid proper attention to it and by submitted definite proposals with cost in consultation with the Director of Public Health. The Chief Engineer may be requested to make a personal inspection with the D.P.H. and submit definite proposals with estimates before the end of this month.

11/4/42

Submitted with a draft letter to Ch Engineer for approval

13/4/42

(Issued in RD/W 8076 dated 13/4/1942)

(21)

Treatment of tanks in and around Mysore city for anti malaria purposes.

(b

Public Works Secretariat | File No 590/PM of 191

Serial No

Letter No 2044 dated 29 7 42 from the Chief Engineer of Mysore.

P

Forwards the note of the Director of Public Health embodying measures proposed for treatment of tanks in and around Mysore city for anti-malaria purposes.

'P'

It is seen from the note that the tanks to be treated are –

1 – Karanji Tank
2 Gobbikere Tank
3 Kukkerahalli Tank
4 Doddakere Tank –

A few of the works mentioned in the Directors note are being attended to by the Health Dept, and the Chief Engineer proposes that the entire proposals may be worked out by that Dept to avoid confusion

The question of treatment ~~of~~ of tanks in and around Mysore city has been pending since Nov 1941. There are four tanks which require to be drained and their feeders diverted for improvement of the health of the town. As some of the works have already been taken up by the Health Dept, the entire work may be entrusted to the Sanitary

bm 29/7/18

Note — Contn sheet

WF 01094—G1 B—20,000—22 2 41

Treatment of limbs in and around Mysore City for autumn & tropical purposes

1033

Bureau as proposed by the Chief Engr. The Board will, however, assist in the preparation of estimates for anti malaria

5/8/42

Dewan
Mr Land Secy

7/8/42

GOVT OF MYSORE

7-8-42

Minute of S G
Dewan

OFFICE OF THE MINISTER FOR L S G & P H
Date 5-8-42
No 1378

The Dir of P H is requested in consultation with the P W D to submit definite proposals to Govt within two months

1528

13 8 42

15 Min
18/8/42

C T O FOR L S G & P H
Date 18 8 42
No 1605

18 8 42

16-8-42

16 For the issue of orders

Asst Secy to M R
19/8

19/8

19/8

17 Draft submitted for approval

27 8 1942

27/8

18 Issued
27/8

The Dir of P H
No S 2785 dated 28 8 42

Re treatment of limbs in and around Mysore

Reminder to issue on 28 10 42. If no reply to receive by then

28/10/42

Issued 5452 d 31 10 42

GOVERNMENT OF MYSORE

DEPARTMENT OF PUBLIC HEALTH

3800/gm

P. PARTHASARATHY L M S B S S C
L R C P L R C S D T M D P H
DIRECTOR OF PUBLIC HEALTH

A S VENKATACHALAM L M S D P H
SUPERINTENDENT

BUREAU OF MALARIOLOGY
SESHADRI ROAD

TELEPHONE No 7144
TELEGRAM HEALTH

No B M 1454
Encl Encl 1

Bangalore, (S India) dated 8th January 1943

To

The Secretary to Government of Mysore,
Law Department,
Bangalore.

Sir

SUB Treatment of Tanks in and around Mysore City for antimalarial purposes

With reference to your letter No G. 2785 dated 18-8-42 and subsequent reminder No G 7437 dated 17-12-42, on the above subject, I have the honour to state comprehensive estimates amounting to Rs 49,800/- for the above works have been sent to the Chief Engineer of Mysore with this office No B M 1427 dated 7-1-1943, for remarks, Copy enclosed for information of Government On receipt of the estimates from the Chief Engineer, the same will be submitted to Government for sanction

I have the honour to be
Sir,
Your most obedient servant,

DIRECTOR OF PUBLIC HEALTH

Submitted for Mysore estimate
further report will be
awaited & approved
13.1.43 20 Jn Pennel
Law Secy
MSSR

B.M 1427 dated 7-1-43 from
Health, Bangalore, to the Chief
Mysore, Bangalore

Sub: Comprehensive estimate amounting to Rs 49,800/- for treatment of Tanks and water courses in and around Mysore City for anti-malaria purposes

In enclosing herewith the above estimate for favour of your perusal, I have the honour to state that the areas proposed to be attended to for anti-malaria work are, (1) the valley behind the His Highness's Bodyguard Lines commencing from the Lucerene Garden to Goblikatte Tank, (2) Karanjikere, (3) Dodkere valley, and (4) Kukkarahalli tank and valley The area to be attended to has been inspected by you conjointly with the undersigned, the Sanitary Engineer, and the Superintending Engineer, Mysore Circle The proposals are in accordance with the scheme of anti-malaria work contemplated in this office letter No B M 149 dated 16-6-1942 addressed to the Chief Engineer I request that the estimate and the scheme as prepared be perused and returned with your remarks if any

8/1/43
DIRECTOR OF PUBLIC HEALTH

MSSR

GOVERNMENT OF MYSORE

DEPARTMENT OF PUBLIC HEALTH

4233

P PARTHASARATHY L M S B S SC
LRCP LRCS DTM DPH
DIRECTOR OF PUBLIC HEALTH

TELEPHONE No 2144
TELEGRAM HEALTH

A S VENKATACHALAM L M S D P H
SUPERINTENDENT

BUREAU OF MALARIOLOGY
SESHADRI ROAD

No B M 1370
Encl

Bangalore (S India) dated January 25, 1943

To

The Secretary to Government,
P W & Ry & Elect Department,
Bangalore

Subj Treatment of Tanks in an around Mysore City for antimalarial purposes

---

With reference to your letter No G 8090 dated 8 1 1943 on the above subject, I have the honour to enclose herewith a copy of this office letter No B M 1454 dated 9 1 1943 addressed to the Secretary to Government, Law Department, for information of Government

I have the honour to be
Sir,
Your most obedient servant,

Director of Public Health

p t o

arams.

4235

Bureau ce
hill, however

Copy of letter No B.M 1454 dated 9.1 1943 from the Director of Public Health in Mysore, Bangalore to the Secretary to Government, Law Department, Bangalore

---

Subject - Treatment of Tanks in and around Mysore City for antimalarial purposes

---

With reference to your letter No-G 2785 dated 18 8 42 and subsequent reminder No G 7437 dated 17 12 1942, on the above subject, I have the honour to state that comprehensive estimates amounting to Rs 49,800/- for the above works have been sent to the Chief Engineer of Mysore with this office No B M 1427 dated 7 1 1943, for remarks Copy enclosed for information of Government On receipt of the estimates from the Chief Engineer, the same will be submitted to Government for sanction

---

This is in reply to a routine reminder issued from this office. The letter addressed to Law Dept has been perused by the minister. The further report promised will be awaited as finally approved thereon and then the bill will be referred to P to Secy for needful action. Submitted for perusal

27 1 43

Law Dept

by
29 1

Cus
30-1-43

28/1 9051

CONTO

Treatment of tanks and water courses in and round Mysore City for anti malaria purposes

4378

Letter No. D M 1639 dated 30 1 1943 from the D P H forwarding an estimate amounting to Rs 49 800/- for treatment of tanks and water courses in and around Mysore City for anti malaria purposes

This is a matter in which action has perhaps to be taken in P W D If approved this will be transferred to P W D Secy for favour of needful action Submitted for orders

2 2 42

It may be sent to the W D Secy for further action

(Law - Secy)

4 2

Secy PWD

Cus 5-2-43

The Comprehensive estimate for the above work is for Rs 49,800/- As there is no specific grant for the purpose, the Chief Engineer may perhaps be consulted as to the source of meeting the cost, and the grant required during the current year

Chief Engr

11/2/43

Returned, with compliments

As the treatment of tanks and water courses in and around Mysore City is exclusively on consideration of health the cost of the work is a legitimate charge on the funds of the

Treatment of tanks and water courses in + around Rayapuram city for anti malaria purposes

13) 370/43

Information Sheet. File No / Current No of 4-71 Page

the Department of Public Health

U O 515. 9 27/2/43

31) The particulars regarding the grant required during the current year may therefore be kindly obtained from the Health Department

1/3/43

Secretary to Government, I
Public Works Department I

A K /26-27th

2/3/43

As opined by Chief Engineer, the Cost of the above works seems to be a legitimate Charge on the funds of the Public Health Dept The Law Secy may perhaps be Consulted

Law Secy 8/3/43

33 The Director of Public Health with if approved, be consulted re to Law Secy)

34 10-3-43

U O no 285/42-43 10 3 '43

35 Forwarded unofficially, with copy of the Director of P H for favour of his information

K R Ramachandra
for Law Secy

B M-2132/Misc file

Retransmitted with compliments.-

36 The estimate for Rs 49,800/- provides for subsoil drainage of Kukkarahalli tank, feeder channel to Karanjikere, Lucern garden, Goblikere, Karanjikere, Dodkere tank bed and the Halladakeri area All the works proposed are for the permanent prevention of mosquito breeding places as also lowering subsoil water table The works proposed are to improve the health conditions of the different localities within the municipal area of Mysore City The cost of these works, therefore, will be a legitimate charge on the Mysore City Municipality as well as the Trust board Some of these works are being done piece-meal and to avoid overlapping it is necessary that the whole programme be taken as one unit and executed in stages as funds permit The Public Health Department, as such, has no funds to provide for these works

27 3 1943

Director of Public Health

(37) Submitted with reference to para 33 supra. In the circumstances stated by the Dr P.H. the matter is hereby referred to L S G for favour of necessary further action, in view of the Notes -

(38) Refer para 14 of the Minutes of the Municipal Commissioner's Conference held on the Director's view above, especially as the works benefit localities within the municipal area. But whatever source meets the cost, the works are perhaps urgent. The L S G Bd may be requested to consult the Mysore City Mun Cl or the Trust Board. The latter derives its funds from the Grant Fund

39 This file will be transferred to L S G Bd

L S G Bd)

4378

40) Treatment of water courses & lands round ~~[illegible]~~ which impounding as an anti malarial measure

41) The estimates & plans together with the report accompanying will be sent to the President, impounding related

A with a request to consider the question in consultation with the Chief & the Trust Board and forward definite & practical proposals before the end of

11964 3/4/43 May 1943.

42) refer paras 14, 15 & 36 Supra

Lawsey 3/4/43

43) A May be advised

Mackenzie 3-4-43

44) Done 3/4/43

45) Draft letter to the PM C R C please for 15 inst

46) Noted with a draft letter for appl

47) Issue advice

OFFICE OF THE MINISTER FOR L S G & P H
Date 13 4 1943
No 8204

12/4 19/4

6479

Continuation Sheet | File No / Current No | of | Page

To the Dcn, cff mnl cl, Mysore
No L10441 Dt 24-4-43
Requests him to consider the question, in consultation with the mnl cl and the cff Impt T Bd and submit definite proposals before the end of May 1943 for the orders of Govt.

From the Dr of P Health
No BM 2335 Dt 21-4-43
Forwards an estimate for Rs 2,500/- for breaching Basappanakatte behind Saraswathipuram, Mysore.

48) The estimate for Rs 49,800/- for the treatment of tanks and water courses in and around Mysore cff for anti malaria purposes has been sent to the Dcn, cff mnl cl, Mysore with a request to submit definite proposals in consultation with the cff mnl cl & the Trust Board

49) The present estimate for Rs 2,500/- will also be sent in continuation

A draft letter is however submitted for orders

KVG 7/4

50) Issue as 28/4/43

TYPE SECTION
23 APR 1943

To the Dcn cff mnl cl, Mysore
No L10691 Dt 1/5/43.
Forwards in original a plan & an estimate for Rs 2,500/- for breaching the Basappanakatte

Sustain 7/5

Letter No B M1304 dt 27-2-45 from the Dr of P Health requesting early orders in regard to his proposal for the treatment of tanks and water courses in & around Mysore City for anti-malaria purposes estimated to cost Rs 49,800/-.

5) The Dept, City Mun Cl, Mysore was requested in this office letter No L10441 dt 24-4-45 to consider the question, in consultation with the Mun Cl & the City Improvement Board & to submit definite and practicable proposals for the orders of Govt No reply has been received so far

Is submitted with a draft letter for to the Dept, City Mun Cl, Mysore asking him to state in what stage the question is at present

Illegible 27/3

Issue at once

[Both the C.W & the file register keep (for days) have slept with this file, without issuing a single reminder for over a year. This is very unsatisfactory]

Issued No L9741 dt 28/

5902
L

Letter No D2 C-85/44-45 dt 8-3-45 from the Chairman, C D V Bd, Mysore, requesting that an estimate for Rs 49,000/- submitted by the Dr of P Health for the Drainage of the Doddakere Tank, may be sanctioned early

54) The connected file on the subject is put up. The Dcdt, City Mnc Cl, Mysore was requested in this office letter No L 10441 dt 24-4-43 to consider the question of the treatment of water courses in & around Mysore, in consultation with the Mnc Cl & the City Improvement Trust Board & to submit definite proposals for the orders of Govt. As no reply has been received so far he has been reminded in the matter on 28-3-45.

55) If approved, the receipt of proposals from the Dcdt, City Mnc Cl, Mysore will be awaited.

Ulks 31/3 S/8 For perusal. The receipt of information called for from the Dcdt. Mysore City Mnc will be awaited

(Asst. Secy) for Secy

57) Mr Ur has attention to the request for an interim reply

[illegible]

5 902 / 7275

58 Submit with a draft letter for appl.
UKB 4/4

59) Immediate
for [illegible]

To the Chairman, CDT Bdl. & ors.
Ref. No. R 10057 & 7425

Subt. Calls for some information

Letter No. M5.181-622 & 2-5-45 from the D.O.C., Cif. Mech. Mysore furnishing the information

61) The M.C. have resolved to request the Trust Board to take up the work urgently and accordingly a letter was addressed to the Chairman in this behalf. The estimate prepared in the year 1942 was for Rs 49,000 & that the same estimate has gone up to 1,40,000 subject to Government orders.

UKB 6/5

61) Is the work referred to by the Chairman of the Trust Board in his letter dated 8th March 45 included among the several items, the list of which has been sent to the Govt? If so what is it? Pl. enquire
for [illegible]

62) Submit with a draft letter for appl.
UKB 12/5

Immediate
for [illegible]

1070/K

The Chairman, City Trust Board
No 111/41 d 17-5-45
Calls for certain information

(63) Submit with a draft reminder

Sec A

No 128
From the Chairman, City Trust Board, Mysore
D 2-C-85/44-45, d 11-8-45

Calls for sanction the revised Estimate amounting to Rs 1,40,000/ for the treatment of tanks and water courses in and around Mysore city for anti-malaria purposes and adds that the Scheme has been worked out by the Director of Public Health

(64) The question of treatment of tanks in and around the Mysore city for anti-malaria purposes is under consideration since Nov 1941

(65) During January, 1943 the Director of Public Health submitted an Estimate for Rs 49,800/ for the treatment of tanks and water courses in and around Mysore which provided for subsoil Drainage of Kukkarahalli Tank, feeder channel to Karanjikere, Lucern garden, Gobbikere, Karanjikere, Doddakere Tank bed

and Hallada kevi area The works proposed were intended to improve the health conditions of the different localities within the Municipal area of the Mysore city The Director of Public Health had therefore recommended that the cost of the scheme might be borne by the Mysore city Municipality and The Trust Board

(6b) The above view was accepted by the Government, and in this office letter No L 10441 d 24-4-43, the President Mysore City Municipal Council was requested to consider the question in consultation with the Municipal Council and the Trust Board, and to submit definite and practical proposals

His V'

(6c) The Chairman, Mysore City Improvement Trust Board has now submitted a revised estimate amounting to Rs 1,40 000/ for the above work, as per current schedule rates, which includes a sum of Rs 8000/ towards Establishment charges and it is stated that the Director of Public Health has prepared the above scheme

(6d) The Trust Board have approved the

1070/L

Serial No

above revised estimate, and have requested that the amount may be provided by the Government early as the work is most urgent and necessary in the interests of public health

69) It is not clear from the Chairman's letter whether the Trust Board want a grant or a loan from the Government to meet the expenditure

70) only the abstract estimates have been sent for Rs 1,40,000 Detailed estimates if prepared will be called for & referred to the Chief Engineer for scrutiny for opinion in the first instance

14/8

ADDITIONAL SECRETARY No 1133 Date 25/8 GOVERNMENT OF MYSORE

24/8/45

71) Yes

25/8

25/8/45

72) Send with a draft letter

73)

27/8

28/8/45

To The Chairman C & T Board Bylaxe
L 20 29 D 14-9-45
Returns the enclosures and calls for detailed Estimate for the works, if they have been prepared

TYPING 29 AUG 1945 GEN & R

NOTE—Contn Sheet

1685 / 720

File No of 194

General and Revenue Secretariat

Serial No

Letter No C 85/44-45 dated 1-9-45 from the President, Mysore City Municipal Council, addressed to Revenue stating that the estimate for treatment of tanks and water courses in and around Mysore, has been submitted to Govt etc

74) Orders of the Dewan

"May be expedited"

Sd/- N M

75) The estimates received from the President were only rough estimates providing lumpsum provisions. They were returned to him on 13-9-45, for resubmission, with detailed estimates

76) The receipt of the detailed estimates will be awaited

77) Refer para 74 supra

Ad seq) for 15/9/45

78) Dewan returned these Estimates

Dons 15/9/45

15/9/45

From the Chairman, Mysore C & T Board D 2-C 85/44-45, d 29-9-45 states that the detailed estimates for the anti-malaria engineering works in and around Mysore, may be got verified by & obtained from the Director of Public Health

Sus B)

17/5 15/9

1618 ✓ 1720 ✓ 2448 ✓ 3578 ✓ 3327/K

79) Submit with a draft letter to the Director of Public Health requesting him to forward the detailed estimates

SO) Jones
MOH
18/10

Sn 13/10 JD 16/10

To the ~~Director~~ Director of Public Health

L 3248 D 22-10-45

Calls for the detailed estimate for the treatment of tanks and water courses in Mysore

From the Director of Public Health

B II 671/45-46 dated 14-11-45

States that the detailed estimate for the anti-malaria works would be submitted on receipt of the original estimate from the Chairman, Mysore T & T Board

Sus A)

81) Submit with a draft reply to the Director of Public Health

SO) Jones
Sn
6/12/45

Mr 6/12

To the D P H - 6/12/45

L 4759 D 7-12-45

calls for information

Sus A)

4272

12 72 J 3327 J 4810

From the Chairman C & T-Board, Mysore

D 2-C-85/44-45-d 12-12-45

States that the detailed estimates have been sent to the Director of Public Health who has acknowledged the same

83) Submit with a draft reminder to the Director of Public Health

27/12

29/12/45

To The Director of Public Health

L6601 dated 11-1-46

Reminds

TYPING SECTION
2 JAN 1946
GEN. & REV. SECTT

from the Director of Health

states that the President, Mysore City Municipality may be requested to furnish the data on which the original Estimate was revised, etc

Submit for Perusal

85) The D of H can himself get the information required from the President, Mysore City Municipality and send the Estimate to Govt

86) without further delay

16/1/46

16/1/46

3

H 810/L 5538/L

To

The Director of Public Health

L 69 23 d 18-1-46

To calls for the detailed estimate in a week

89) Sent with another D.O. reminder

By Immediate

for 31/1/46

31/1

To the D.P.H.

L 7833 d 4-2-46

Reminds

TYPING SECTION
31 JAN 1946
CTH & REV SECTT

From the Director of Public Health

B.M. 1163 dated 7-2-46

Returns the detailed estimate for Rs 1,40,000/ for the treatment of tanks in and around Mysore city, for anti-malaria purposes after due verification by the Sanitary Engineer.

89) The history of the case has been explained at paras 64 to 70 of the Notes Supra

90) The amount of the estimate has now come to Rs 1,40,000/ according to

current Schedule rates, against Rs 49800/ in the year 1942. The details of works, and variations are noted below –

	Original Estimate Rs	Revised Estimate Rs
1) Sub-soil drainage in the rear of Kukkarahalli tank –	5700	14,055
2) Improving feeder channel to Karangikere –	3100	7635
3) Sub-soil drainage to Lucerne garden –	3630 –	11,975
4) Sub soil drainage to Gobikere –	8320	18,450
5) " drainage to rear of Karangikere –	3350 –	10,375
6) " drainage to Doddakere Tank –	10,000/	32,375
7) " Subsoil drainage to Halladakere –	15,700 –	36,270
Total –	49,800 –	1,31,135
Add Establishment –		8000
		Rs 1,40,000

VI) From the above, it is seen that the Breaching of the Basappana Katte behind the Saraswathipuram get an estimated cost of Rs 2500/ is

Plan may be taken up after the [illegible] are completed

Serial No

not included in the above comprehensive estimate

92) The Chairman, Mysore C & T Board has requested the Government to provide funds to the extent of Rs 14 lakhs being the estimated cost of the works

93) This is one of the urgent and important works included in the current year's Budget Estimate of the Trust Board and for which he had asked for an additional grant But as the concerned estimate for the work had not been sanctioned, this item was ordered to be deleted from the sanctioned Budget

94) ~~Refer~~ The Sanitary Engineer has duly scrutinised the estimate for Rs 140,000/

95) Refer - paras 70 to 73 Supra

96) This is a question which is pending disposal from the year 1941

97) The anti-malaria measures proposed in this case would also improve the health of the people of the municipality It is therefore incumbent on the part of the municipality that to meet a moiety of the above cost amounting

NOTE—Contn Sheet

to Rs 70,000/- The remaining half will be met by the Trust Board and the Govt will have to give an additional grant to the Board to the extent of Rs 70,000/-

9(8) If the above proposal is approved, the Hyderabad Govt will have to be consulted as to their willingness to contribute a moiety of the estimated cost

9(9) The works, if sanctioned, will have to be carried out by the Sanitary Bureau under the control of the Chief Engineer for Irrigation

(10) The works may be spread over a period of two years. There are hardly four months more for the year to close, it may not be possible to carry out works for more than Rs 40,000/- during the current year. In view of the urgency & importance of the work, the Scheme may perhaps be approved and ordered to be started immediately with a grant of Rs 40,000 this year.

The question of apportioning the expe between the H.E.C. & the Trust Board

Govt 14/9/46

Serial No

May be examined in the meanwhile & separate orders passed.

(97) The Secy may be consulted in regard to the add grant this year to the Trust Board

S'8 45/14/N

(10?) As the Sanitary Engineer has duly sanctioned the estimate for Rs 1-4 lakhs, it may not be necessary to consult the chief Engineer, ~~again~~ in view of the urgency of the matter. Refer paras 70 & 71 supra

Reply for 13/2/46

14/N

(103) The Estimate for Rs 1.4 (three) lakhs may be sanctioned subject to revision if necessary by the Chief Engineer for Irrigation

(104) The work may be ordered to be taken up on a rush basis subject to the following conditions

1/2 the Estimated Cost to be borne by the Municipality & Trust Board in Equal

NOTE—Contn Sheet

Anti malaria Works - Mysore City

File No 5 of 194 | General and Revenue Secretariat

Serial No

proportions

2) The other half be given by Govt as an outright grant

3) The work be proceeded with during the Current year out of Municipal funds & Trust Board funds either by reappropriation or by Closing Balance —.

4 The work to be done by the Sanitary Engineer which involves control by the Chief Engineer for Irrigation.

5) The work to be taken up vigorously & completed before the end of the next official year

6) Due provision be made in the Budget for 46-47 for Govt Share of the Cost of the Scheme

Minister for Edn & PH
through Jt Secy.
14/2

U.O.No. 5210

These estimates were prepared in 1942 At that time, the cost was Rs 73,800/- The present cost is Rs 1,31,000 Obviously the estimates are not urgent, because if they were prepared in 1942 and have been

Treatment of tanks and water courses in and around Rajpore City for anti-malaria purpose

Serial No

52107

submitted only now, they could presumably wait till the rates go down. Further, I may state that some of these works as I know have already been partly done by the Trust Board or by the Health Department For example, part of item o 1 has been attended to by the Trust Board and a part of items 4 and 5 have also been attended to Regarding these estimates themselves I do not wish to offer remarks except to state that when I was the Chairman of the Trust Board I felt that the estimates were capable of considerable revision In any event, there is no urgency about this

OFFICE OF THE MINISTER FOR EDUCATION & F
Date 20/2/46
No 5028

18/2

19/2/46

(ob)
Action may be taken as suggested by the Rev Secy
If there are any items in respect of which work has already been done, as pointed by the Jt Secy the Ch Engineer will take due note of them while scrutinising the estimates
Dewan)

OFFICE OF THE MINISTER FOR REVENUE
No
Date
MAN'S OFFICE
9 MAR 1946
5371

NOTE—Contn Sheet

File No. of 194 | General and Revenue Secretariat

Serial No

107. Some of the works are evidently more urgent than the rest – I should give priority to (1) Kattarambakkam (6) Ottadakare + (7) Hallidakere drainage schemes These may be taken up first, and completed quickly ~~after~~ the relative estimates ~~have been~~ may be examined and items which have been completed may be deleted The works may be carried out by the Irrigation Board – with the advice of the Sanitary Engineer

531

L. [illegible] LFT [illegible] OTER FOR EDUCATION [illegible]
Date 22 4 46
No 6478

[illegible]
21/4/46

22/4/46

23/4

108) Submit with a draft letter for approval

109) The question of financing the works can be considered when the revised estimates are submitted in this behalf

[illegible] 24/4

[illegible] 26/4/46

110th) Perusal by Flood Issue after [illegible]

[illegible] 27/4

FINANCE CO II 7153 29/4

111) Please to add remarks The work cannot be started (a) before [illegible] (b) before [illegible] Revised [illegible]

[illegible] 1/5/46

7338

(12) Why the draft as revised by the Finance Secretary issue?

(13) Issue

2/5/46

To The Chairman, C S T Board, Mysore

L 12240-2, M 92-45-2 of 4-5-46

issues instructions accordingly and calls for revised estimates

Copy to. Director of Public Health

Chief Engr for necessary action

(14) P A to the Minister for E&M, P W and Forests

7/5/46

Recd of the figures from the Minister here

From the Director of Public Health

B M-1873, dated 13-5-1946

States that his office cannot take any action in the matter of re examining and modifying the estimate for Rs 1,40,000 - for the anti-malaria works in and around Mysore City, as the Bureau of Sanitary Engineering has since been transferred to the control of the Public Works Dept

85445 8618 5 7335/2

From the Chairman, C.S.I. Board, Mysore
D 2-C 85/44-45, dated 21-5-46

Forwards a copy of the letter addressed from to the Director of Public Health requesting to duly revise the estimate for Rs 1,40,000- for treatment of tanks and water courses in and around Mysore city, for anti-malaria purposes

(15) In view of the circumstances mentioned by the Director of Public Health the Chief Engineer for Irrigation will be requested to revise and resubmit the above estimates, in consultation with the Director of Public Health and the Chairman, C.S.I. Board, Mysore

(16) A draft is put up, for appl.

Recommended
8/6/46

(17) Issue orders
8/6

TYPING SECTION
10 JUN 6
GEN

To the C.E. for Irrigation
X 13879 dated 4-6-46
calls for estimate

Mr 1/6?
Recd by me
8/6/46
Sirs A

245 no 18/f

From the Chief Engineer for Irrigation

3054/S dated 25-6-46

Requests return of the original estimate for treatment of tanks and water courses in and around Mysore city for anti-malaria purposes

(1) The estimate is not in this office

(2) A draft reply to C.E. is put up

(3) [signature]
3/7/46

1/7

To the C.E. for Irrigation

L 200 dated 4-7-46

Directions to return the estimate, given by D.P.H.

L 200 dated 4-7-46

Pls copy to D.P.H.

TYPING SECTION
3 JULY 1946

From the Director of Public Health

B.M. 103, dated 9-7-46

Pls a copy of his letter addressed to the Chairman, C.I.T. Board, Mysore, in the matter

24 S 45 25 45 3

That he is not aware of any of the items or part thereof of the works provided for, in the estimate for Rs 1,40,000/

From the Director of Public Health.

to M 105/46-47, dated 8-7-46

Forts a copy of his letter addressed to the Chief Engineer for Irrigation forwarding seven estimates relating to the treatment of tanks and water courses, in and around, Kyaw city

(20) The receipt of the Revised estimate for the above work from the Chief Engineer for Irrigation, will be awaited, till 8-8-46

(21) What is the progress made further in regard to the estimates in the State Budget of 1946-47?

Mr 27/7

for 27/7 Ins

(22) A provision of Rs 82,000/ has been made for this work, in the next year's State Budget

(23) Please see the letter received today from the Chief Engineer for Irrigation & Works as if the sketches have not yet been rec'd from us. Pl pursue up

Mr 30/7

Dy Sec

for 31/7 Ins

1023 / 5 453 / L

From the Chief Engineer for Irrigation
23715 dated 30-7-46

States that action is being taken to get the necessary estimates for the anti-malaria works in and around Mysore city

(24) It is ascertained from the Chief Engineer's office that the Director of Public Health has been addressed to return back all the connected estimates

A/ (25) Further report from the Chief Engineer will be awaited till 25-8-46

(26) A - has been recd today PL put it up

10/8

From the Chief Engineer for Irrigation
40575, dated 10-8-46

States that the estimates & plans have just been received, that he would inspect it on 14-8-46 and would furnish his remarks thereafter

(27) Further report from the Chief Engineer will be awaited - till the end of the month.

Sus A) 22/8

1296
L

128) A draft reminder to T&E for institution
is put up 129) This has been recd today
[illegible]
2/9/46

2/9

From the Chief Engr for Irrgn
573/5, dated 31-8-46
states that, in connection with the
anti-malaria measures, the several tanks in and
around Mysore city have been inspected jointly by the
Chairman, C&T Board, Chief Engr Roads & Buildings &
Health Officer and himself, and that he has given
instructions to the Trust Board Engineer to prepare the
concerned estimates
The above reports for perusal
130) A draft letter to the Chairman, C&T Board,
Mysore, requesting him to send the estimates to the
Chief Engr very early is put up

In appl

2/9

Rec secy) 2/9/46
131) Done above
3/9/46

MAIN SECTION
[illegible]
[illegible]

C 574 | 46-47 Sp 12/10

1286 | 1749 | 3380

The Chairman C S T Board, Mysore

K 3259 d 5-9-46

Requests him to send estimates to

Chief Engr

132) A draft reminder to the Chairman is

Put up

133) Issue above

11/10

26 10 46

To The Chairman, C S T Board, Mysore

K 5308 dated 30-10-46

Reminds

From the Chairman C S T Board, Mysore

states that the concerned estimates for

Doddaleere tank were sent to the Chief

Engineer for sanction on 26-10-46

134) Submit with a draft D O reminder

to the Chief Engineer for sanction

135) Approved over to secy for signature

11/11/46

To C.E for sanction

L 5816 dt 12-11-46

Reminds

10/11

3932 — 3380

From the Chief Engr for Irrigation

1000/S dated 21-11-46

States that the estimate amounting to Rs 69,000 received from the Chairman, C & T Board, Illyas, been sent to the Chief Engr for Roads and Buildings for remarks and that further action would be taken on its receipt

136) Issue Sft letter pointing

for

287 12/46

To The C E for Irrig

5956 d 30-11-46

Reminds for the estimate

From the Chief Engineer for Roads & Buildings

5753 d 10-1-47

States that the estimate in connection with the treatment of tanks and water courses in and around Illyas would be sent only on receipt of certain particulars called for from the Chairman, C & T Board, Bangalore

137) A draft letter to the Chairman,

5527 & 3932

City Improvement Trust Board, Mysore,
requesting him to furnish the particulars
called for by the C.E. for roads, in connection

The 17/1/47 138) For approval of the draft letter putting (Sanctioning the this expenditure grant has been pending disposal of the annual set report for this year in the State Budget is not likely to be spent this year)

SYFIG SECTION
21 JAN 1947
WORK & REV SECT

17/1/47

139) Issue
DDX 20/1/47

To the Chairman C.I.T. Board
Mysore
Lto 3465 dt 22-1-47

Remarks

From the Chairman, C.I.T. Board, Mysore
D3 C-105/45-46 dated 29-1-47
states that all the particulars required by
the Chief Engineer were furnished on 21st inst.
(46) submit with a draft reminder to the
C.E. for Roads & Buildings
(41) 12/2/47

12/2/47

5527 / 7694

The Chief Engineer for Roads & Buildings
L 11475-d 20-2-46
Reminds

Enclosed

From the Chief Engineer for Irrigation
1916/5 dated 15-3-47

Pds for sanction, an estimate for
Rs 79,100- for draining of the Doddakere
Tank bed Mysore, as an anti-malaria
measure

(47) In accordance with the Dewan's Minute
dated 21-4-46, in this office letter no L 12240
dated 4-5-1946, the Chief Engineer for Irrigation
was requested to show priority for the
marginally-noted works, in connection with
the anti-malaria measures
to be carried out
in and around Mysore
City and necessary
estimates were called for from that officer

vide para (7) below

1) Kukkarahalli Tank
2) Doddakere
3) Halladdakere drainage scheme

See Flag 'A'

143 The Chief Engineer for Irrigation has not yet submitted estimates for items 1 and 3 (i.e Kulkavathalli Tank and Hallaballare Drainage scheme)

144 It is reported that the Doddaballare tank bed is very much undulated and contains a number of pits where water stagnates and gives room for breeding of mosquitoes With a view to see that the bed of the tank is properly drained off and the contour channel in the tank bed is graded properly, after the removal of silt, etc, the Chief Engineer for Irrigation has forwarded for sanction an estimate for Rs 79,100- for draining off the Doddaballare tank.

145 A provision of Rs 82,000- has been made for ~~this~~ anti-malaria measures and improving work, in the current year's State Budget

7677 / 5527
2

146) The proposal to sanction the estimate for Rs 79,100- for draining of the Doddakere Tank bed, is put up for orders

147) The works will be carried out by the C & T Board - Mysore - with the advice of the Sanitary Engineer

18/3/47

148) The estimate for Rs 79,100/- for the above work may be sanctioned in consultation with the Financial Secretary

If the cost of the estimate is more than Rs 25,000, it will have to be treated as Council matter

Sd/- [illegible]
18/3/47

149) The estimate may be sanctioned

This may be disposed of by circulation. [illegible] 20/3

150) [illegible] 25/3/47

20/3/47

FINANCIAL SEC
U O No F
6489
20/3
BAN

Fort Elec 24/3
Date
No 6419

7679
2

Submit with a circulation note for approval

Rev Secy for 29/3/47

29/3/47

TS PI type copies above

for 1/4/47

SECTION
2 APR 1947

Typed copies are placed below for being sent to the Chief Secy

Rev Secy for 5/4/47

3/4/47

Chief Secy

6/4 for 7/4/47

Council File No 0431/4
FOR DISPOSAL BY CIRCULATION
10/4/47

7/4/47

Vic
Rev

15/4/47

16/4

OFFICE OF THE MINISTER
FOR EDUCATION & P H
Date 21 4 47
No. 6688

D F.N please

for 16/4/47

Submit with a D F.N. for appr

Rev Secy for 17/4/47

17/4

Chief Secy for Education & P H.

18/4

Two copies of signed 7 N put up

10/5

CIRCULATION

Draining off Doddakere tank in Mysore City as an anti-malaria measure

The question relating to the treatment of tanks in and around the Mysore City, for antimalaria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs.40,800/- for the treatment of tanks and water courses in and around Mysore City, which provided for sub-soil drainage of Kukkarahalli tank, diverting the feeder channel to Kerangikere, and draining the Lucker garden area, Goblikere, Doddakere tank bed and Halladakeri area.

As the works proposed were intended to improve the health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council. The Mysore City Municipal Council has pleaded its financial inability to meet the expenditure on these works.

In February 1946 the Director of Public Health forwarded for sanction a revised estimate for Rs.1,40,000/- based on the existing schedule of rates for these works Some of the works included in the above estimate were found to be more urgent than the rest In accordance with the Dewan's minute dated 21st April 1946 the following instructions were issued -

(a) that priority be given to Kukkarahalli and Doddakere tanks and Halladakere Drainage scheme which may be taken up first and completed quickly,

(b) the relative estimates may be examined and items which have been completed may be deleted,

(c) the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer.

The Chief Engineer for Irrigation has accordingly forwarded for sanction, an estimate for Rs.79,100/- for draining off the Doddakere tank as the sub-soil drainage in itself would not be effective. It is proposed to grade the tank bed suitably after removal of silt and to canalise the area with rough stone channels. With a view to eliminating the stagnation of water in pools in the bed of the tank, after rains, necessary provision for proper drainage, lowering the draft channel, construction of weirs and bridges for the use of pedestrians and cattle etc., have been made in the estimate

It is proposed to sanction the above estimate for Rs.79,100, meeting the expenditure from the provision of Rs.82,000/- made for "Antimalaria measures in Mysore City" in the current year's State Budget. The proposal has been approved by the Minister for Education and Public Health and the file has been ordered to be disposed of by circulation in Council.

Points for orders.

1) Sanctioning the estimate for Rs.79,100/- for draining off the Doddakere tank in Mysore City.

2) Meeting the expenditure in this behalf from the provision of Rs.82,000/- made under the head "Antimalaria measures in Mysore City" in the current year's State Budget.

M. N. Ballegar
Revenue Secretary to Govt.

CIRCULATION NOTE

SUBJECT Draining off Doddakere tank in Mysore City as an anti-malaria measure.

The question relating to the treatment of tanks in and around the Mysore City, for antimalaria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs 49,800/- for the treatment of tanks and water courses in and around Mysore City, which provided for the sub-soil drainage of Kukkarahalli tank, diverting the feeder channel to Karangikere, and draining Lucern Garden, area Goblikere, Doddakere tank bed and Halladakeri area

As the works proposed were intended to improve the health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council The Mysore City Municipal Council has pleaded its financial inability to meet the expenditure on these works.

In February 1946, the Director of Public Health forwarded for sanction a revised estimate for Rs 1,40,000/- based on the existing schedule of rates for these works Some of the works included in the above estimate were found to be more urgent than the rest In accordance with the Dewan's minute dated 21st April 1946, the following instructions were issued -

(a) that priority be given to Kukkarahalli and Doddakere tanks and Halladakere Drainage scheme which may be taken up first and completed quickly,

(b) the relative estimates may be examined and items which have been completed may be deleted,

(c) the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer

The Chief Engineer for Irrigation has accordingly forwarded for sanction, an estimate for Rs.79,100/- for draining off the Doddakere tank as the sub-soil drainage in itself would not be effective It is proposed to grade the tank bed suitably after removal of silt and to canalise the area with rough stone channels With a view to eliminating the stagnation of water in pools in the bed of the tank, after rains, necessary provision for proper drainage, lowering the draft channel, construction of weirs and bridges for the use of pedestrians and cattle etc , have been made in the estimate

It is proposed to sanction the above estimate for Rs 79,100, meeting the expenditure from the provision of Rs.82,000/- made for "Antimalaria measures in Mysore City" in the current year's State Budget The proposal has been approved by the Minister for Education and Public Health and the file has been ordered to be disposed of by circulation. ~~in Council~~.

Points for orders

1) Sanctioning the estimate for Rs 79,100/- for draining off the Doddakere tank in Mysore City.

2) Meeting the expenditure in this behalf from the provision of Rs 82,000/- made under the head "Antimalaria measures in Mysore City" in the current year's State Budget

H N Pallegar
Revenue Secretary to Govt

CIRCULATION NOTE

SUBJECT. Draining off Doddakere tank in Mysore as an anti-malaria measure.

The question relating to the treatment of tanks in and around the Mysore City, for antimalaria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs.49,800/- for the treatment of tanks and water courses in and around Mysore City, which provided for sub-soil drainage of Kukkarahalli and draining the feeder channel to Karangakere, Lucknow Garden, Goblikere area Doddakere tank bed and Halladakeri area.

As the works proposed were intended to improve health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council. The Mysore City Municipal Council has pleaded its inability to meet the expenditure on these works.

In February 1946 the Director of Public Health forwarded for sanction a revised estimate for [illegible] based on the existing schedule of rates for the [illegible] Some of the works included in the above estimate [illegible] found to be more urgent than the rest In accordance with the Dewan's Minute dated 21st April 1946 [illegible] ing instructions were issued.-

(a) that priority be given to Kukkarahalli Doddakere tanks and Halladakere Drainage may be taken up first and completed quickly

(b) the relative estimates may be [illegible] which have been completed may be deleted,

(c) the works may be carried out by the City Improvement Trust Board with the advice of Sanitary Engineer.

The Chief Engineer for Irrigation has accordingly forwarded for sanction, an estimate for Rs.79,100/- for draining off the Doddakere tank as the sub-soil drainage in itself would not be effective. It is proposed to grade the tank bed suitably after removal of silt and to canalise the area with rough stone channels With a view to eliminating the stagnation of water in pools in the bed of the tank, after rains, necessary provision for proper drainage, lowering the draft channel, construction of weirs and bridges for the use of pedestrians and cattle etc., have been made in the estimate

It is proposed to sanction the above estimate for Rs.79,100 meeting the expenditure from the provision of Rs.82,000/- made for "Antimalaria measures in Mysore City" in the current year's State Budget The proposal has been approved by the Minister for Education and Public Health and the file has been ordered to be disposed of by circulation. ~~in Council~~

Points for orders.

1) Sanctioning the estimate for Rs.79,100/- for draining off the Doddakere tank in Mysore City.

2) Meeting the expenditure in this behalf from the provision of Rs 82,000/- made under the head "Antimalaria measures in Mysore City" in the current year's State Budget

Revenue Secretary

CIRCULATION NOTE

SUBJECT: Draining off Doddakere tank in Mysore City as an anti-malaria measure.

The question relating to the treatment of tanks in and around the Mysore City, for antimaleria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs.49,800/- for the treatment of tanks and water courses in and around Mysore City, which provided for sub-soil drainage of Kukkarahalli tank, feeder channel to Karargikere, and draining Luceur garden, area Goblikere, Doddakere tank bed and Halladakeri area.

As the works proposed were intended to improve the health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council. The Mysore City Municipal Council has pleaded its financial inability to meet the expenditure on these works.

In February 1946 the Director of Public Health forwarded for sanction a revised estimate for Rs.1,40,000/- based on the existing schedule of rates for these works. Some of the works included in the above estimate were found to be more urgent than the rest. In accordance with the Dewan's Minute dated 21st April 1946 the following instructions were issued:-

(a) that priority be given to Kukkarahalli and Doddakere tanks and Halladakere Drainage scheme which may be taken up first and completed quickly;

(b) the relative estimates may be examined and items which have been completed may be deleted;

(c) the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer.

The Chief Engineer for Irrigation has accordingly forwarded for sanction, an estimate for Rs.79,100/- for draining off the Doddakere tank as the sub-soil drainage in itself would not be effective. It is proposed to grade the tank bed suitably after removal of silt and to canalize the area with rough stone channels. With a view to eliminating the stagnation of water in pools in the bed of the tank, after rains, necessary provision for proper drainage, lowering the draft channel, construction of weirs and bridges for the use of pedestrians and cattle etc., have been made in the estimate.

It is proposed to sanction the above estimate for Rs.79,100, meeting the expenditure from the provision of Rs.82,000/- made for "Antimalaria measures in Mysore City" in the current year's State Budget. The proposal has been approved by the Minister for Education and Public Health and the file has been ordered to be disposed of by circulation. ~~In Council.~~

Points for orders.

1) Sanctioning the estimate for Rs.79,100/- for draining off the Doddakere tank in Mysore City.

2) Meeting the expenditure in this behalf from the provision of Rs.82,000/- made under the head "Antimalaria measures in Mysore City" in the current year's State Budget.

C. R. Pallegar
Revenue Secretary to Govt.

CIRCULATION NOTE.

SUBJECT: Draining off Doddakere tank in Mysore City as an anti-malaria measure.

The question relating to the treatment of tanks in and around the Mysore City, for antimalaria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs.49,800/- for the treatment of tanks and water courses in and around Mysore City, which provided for sub-soil drainage of Kukkarahalli tank, feeder channel to Karangikere, Lucknow Garden, Goblikere, Doddakere tank bed and Halladakeri area.

As the works proposed were intended to improve the health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council. The Mysore City Municipal Council has pleaded its financial inability to meet the expenditure on these works.

In February 1946, the Director of Public Health forwarded for sanction a revised estimate for Rs.1,40,000/- based on the existing schedule of rates for these works. Some of the works included in the above estimate were found to be more urgent than the rest. In accordance with the Dewan's Minute dated 21st April 1946, the following instructions were issued:-

(a) that priority be given to Kukkarahalli and Doddakere tanks and Halladakere Drainage scheme which may be taken up first and completed quickly;

(b) the relative estimates may be examined and items which have been completed may be deleted;

(c) the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer.

File No 84 3 d/11
DISPOSAL BY CIRCULATION

Order of the Minister for Education & P.H.
Date 15 4 47
No 6557

CIRCULATION NOTE

SUBJECT: Draining off Doddakere tank in Mysore City as an anti-malaria measure.

The question relating to the treatment of tanks in and around the Mysore City, for antimalaria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs.49,000/- for the treatment of tanks and water courses in and around Mysore City, which provided for sub-soil drainage of kukkerahalli tank, feeder channel to Karangikere, and draining the Lucknow Garden, Coblikere, Doddakere tank bed and the Halladakeri area.

As the works proposed were intended to improve the health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council. The Mysore City Municipal Council has pleaded its financial inability to meet the expenditure on these works.

In February 1946 the Director of Public Health forwarded for sanction a revised estimate for Rs.1,40,000/- based on the existing schedule of rates for these works. Some of the works included in the above estimate were found to be more urgent than the rest. In accordance with the Dewan's Minute dated 21st April 1946 the following instructions were issued -

(a) that priority be given to Kukkerahalli and Doddakere tanks and Halladakere Drainage scheme which may be taken up first and completed quickly;

(b) the relative estimates may be examined and items which have been completed may be deleted;

(c) the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer.

The Chief Engineer for Irrigation has accordingly forwarded for sanction, an estimate for Rs.79,100/- for draining off the Doddakere tank as the sub-soil drainage in itself would not be effective. It is proposed to grade the tank bed suitably after removal of silt and to canalise the area with rough stone channels. With a view to eliminating the stagnation of water in pools in the bed of the tank, after rains, necessary provision for proper drainage, lowering the draft channel, construction of weirs and bridges for the use of pedestrians and cattle etc., have been made in the estimate.

It is proposed to sanction the above estimate for Rs.79,100 meeting the expenditure from the provision of Rs.82,000/- made for "Antimalaria measures in Mysore City" in the current year's State Budget. The proposal has been approved by the Minister for Education and Public Health and the file has been ordered to be disposed of by circulation in Council.

Points for orders.

1) Sanctioning the estimate for Rs.79,100/- for draining off the Doddakere tank in Mysore City.

2) Meeting the expenditure in this behalf from the provision of Rs.82,000/- made under the head "Antimalaria measures in Mysore City" in the current year's State Budget.

K N Ballegowda
Revenue Secretary to Govt

File No 1843 d 1/1 d
DISPOSAL CIRCULATION

Finance, Law & Revenue

14/4/47

OFFICE OF THE ... FOR LAW
14 A... 7166
No. ---

CIRCULATION NOTE

SUBJECT. Draining off Doddakere tank in Mysore City as an anti-malaria measure.

The question relating to the treatment of tanks in and around the Mysore City, for antimalaria purposes, is under examination since the year 1941.

During January 1943, the Director of Public Health submitted an estimate for Rs.49,800/- for the treatment of tanks and water courses in and around Mysore City, which provided for sub-soil drainage of Kukkarahalli tank, diverting the feeder channel to Harandikere, drawing the Lucker Garden, cuda Coblikere, Doddakere tank bed and Halladakeri area.

As the works proposed were intended to improve the health conditions of different localities within the Mysore City municipal limits, the question of financing the scheme, from out of municipal funds, was under correspondence with the Mysore City Municipal Council. The Mysore City Municipal Council has pleaded its financial inability to meet the expenditure on these works.

In February 1946, the Director of Public Health forwarded for sanction a revised estimate for Rs.1,40,000/- based on the existing schedule of rates for these works. Some of the works included in the above estimate were found to be more urgent than the rest. In accordance with the Dewan's minute dated 21st April 1946, the following instructions were issued -

(a) that priority be given to Kukkarahalli and Doddakere tanks and Halladakere Drainage scheme which may be taken up first and completed quickly,

(b) the relative estimates may be examined and items which have been completed may be deleted;

(c) the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer.

The Chief Engineer for Irrigation has accordingly forwarded for sanction, an estimate for Rs.79,100/- for draining off the Doddakere tank as the sub-soil drainage in itself would not be effective. It is proposed to grade the tank bed suitably after removal of silt and to canalise the area with rough stone channels. With a view to eliminating the stagnation of water in pools in the bed of the tank, after rains, necessary provision for proper drainage, lowering the draft channel, construction of weirs and bridges for the use of pedestrians and cattle etc., have been made in the estimate

It is proposed to sanction the above estimate for Rs.79,100 meeting the expenditure from the provision of Rs.82,000/- made for "Antimalaria measures in Mysore City in the current year's State Budget. The proposal has been approved by the Minister for Education and Public Health and the file has been ordered to be disposed of by circulation in Council.

Points for orders.

1) Sanctioning the estimate for Rs.79,100/- for draining off the Doddakere tank in Mysore City.

2) Meeting the expenditure in this behalf from the provision of Rs.82,000/- made under the head "Antimalaria measures in Mysore City" in the current year's State Budget.

Revenue Secretary to Govt

Final Note by the Minister for Education and Public Health

***Subject*—** Draining of the Doddakere Tank in Mysore City as an anti-malaria measure

The question of treatment of tanks and water courses in and around the Mysore City for anti-malaria purposes has been under examination in the departments of Public Health and Public Works and the Mysore City Improvement Trust Board for a long time

In February 1946, the Director of Public Health submitted for sanction an estimate for Rs 1,40,000 for the execution of the following works to bring down malaria in the City -

(1) Sub-soil drainage in the rear of the Kukkarahalli tank,
(2) Improving feed channel to Karanjikere,
(3) Sub-soil drainage to the Lucerene garden,
(4) Sub-soil drainage to the rear of the Karangikere,
(5) Sub-soil drainage to the Goblikere,
(6) Sub-soil drainage to the Doddakere,
(7) Sub-soil drainage to the Halladakere

On finding that some of the items provided in the above estimate had already been attended to by the Trust Board or the Health Department and that some of the items required immediate execution, Government issued in May 1946 to the Chairman, City Improvement Trust Board, the following instructions -

(i) that priority be given to the Kukkarahalli and Doddakere tanks and the Halladakere Drainage Scheme, which might be taken up first and completed quickly,
(ii) the relative estimates may be examined and items which had been completed might be deleted,
(iii) the works may be carried out by the Mysore City Improvement Trust Board, with the advice of the Sanitary Engineer

In August 1946, the Chairman, City Improvement Trust Board, Mysore, the Chief Engineer for Roads and Buildings and the Chief Engineer for Irrigation and the Health Officer, City Municipality, after holding joint inspection of the several areas and discussing the relative advantages of the proposed measures, requested the Chairman of the Trust Board to have estimates prepared for the several works on the lines decided at the joint inspection

JPD

The Chief Engineer has now submitted for sanction an estimate for Rs 79,100/- for draining of Doddakere Tank bed prepared by the Trust Board Engineer as per instructions of the joint inspection The estimate provides for the grading of the tank bed suitably, the removal of silt in the tank bed, the canalising of the area with rough stone channels with 1 2 4 cement concrete silk pattern inverts of suitable size, the lowering of the draft channel, the elimination of stagnant pools in the tank bed after rains and construction of necessary weirs and bridges for the use of pedestrians and cattle

It is proposed to sanction the above estimate for Rs 79,100 the cost being met out of the provision of Rs 82,000 made in the budget of the current year under "Anti-malaria Measures in Mysore City"

The Dewan-incharge and the other Ministers agree to the proposal and I solicit the gracious sanction of His Highness to the same

H S Royan

Bangalore
9th May 1947

Minister for Education
and Public Health

Submitted to His Highness

I submit herewith a Final Note by the Minister for Education and Public Health on the proposal to sanction an estimate for Rs 79,100/- for draining of Doddakere tank in Mysore City as an anti-malaria measure, for the gracious sanction of His Highness

g
ti-

H Koyaji

Bangalore,
10th May 1947

Minister for Education and Public Health
in charge of the current duties of the Dewan

Record of Cases submitted for the Orders of

His Highness the Maharaja

No 1142
10-5-47

Subject.

Estimate for Rs 79,100/- for draining of Doddakere tank in Mysore City as an anti malaria measure

Chief Secretary
AHM 16/5

No 1137

Order

SRN
12/5/47

WO
17/5/47

7679/2

21

General and Revenue Secretariat

WD 05304 -GPB—500—11 1 47

SUBJECT —

Estimate for Rs 79,100/- for draining of Doddakere tank in Mysore City as an anti-malaria measure

23 MAY 1947

(*)

14 All urgent or confidential files returned with His Highness's orders may in the absence of instructions or indications to the contrary be ordinarily circulated to the Ministers for perusal after the issue of orders

16 The Secretaries concerned should see that orders in the cases referred to above are issued at once and that the files are returned immediately after to the Chief Secretary for circulation to the Ministers

17 In all other cases the files will first be circulated to the Ministers at Headquarters and then sent to the Secretariat concerned for the issue of orders

Circulated to Council of Ministers for perusal of His Highness orders before/after issue of orders (*Vide* Rules 14 16 and 17 of the Subsidiary Rules of the Mysore Government Business Rules) (*)

Chief Secretary to Government

17/5/47

Through the Secretary to Government Revenue Department

1 Minister for Education & Public Health — 27/6/47

2 Minister for Law — 28/5/47

3 Minister for Agriculture and Public Works — 30/5

4 Minister for Home — 3/6

5 Minister for Revenue and Communications — 4/6

Secretary to Government Revenue Department (with compliments) — 5/6

NOTE —Contn sheet

7629
2

To The Chairman, C.S.T. Board - Mysore
" Chief Engineer for Irrigation
" " for P.W.D.
" President - City Mun. Council Mysore
" Director of Public Health
" Comptroller to Govt.

R/6393-8, dated 26-5-47

Sanction is accorded to the Rs 29,000 for the clearing off of the Dodda Kere tank in Mysore - as an anti-malaria measure.

This will be sent to the Confidential Branch for Completing Circulation

26/5/47

26/5

C WORKS SECRETARIAT

Draft for Approval

No P.W 274/S

Dated 7/11/41

Encl

R PW 4248/S
5/12/41

(1)

FROM

The Secretary to Government,
Public Works Department,

To

The Chief Engineer of Mysore
Bangalore

Subject Treatment of Tanks in and around Mysore city for anti-malaria purposes

Sir,

I am directed to forward herewith a copy of letter No C 1890 dt 1/11/41 from Sir Charles Todhunter offering his suggestions in the matter of treating of tanks in and around Mysore city for anti malaria purposes, and request you kindly to examine the proposals and furnish a detailed report on the subject, together

Sues

~~pilé an extinalé forme wons~~

involved

I have etc

Secy Pwd

3129 (Extn No 2)

IMMEDIATE

WD 1068—G1B—3 000—4 12 26

19

From The Chief Engineer of Mysore,
~~THE SECRETARY TO GOVERNMENT~~,
PUBLIC WORKS DEPARTMENT
Bangalore

To

The Secretary to Government,
Public Works Department,
Bangalore

Dated Bangalore 13th January 1942

Despatched 15/1

Received

General No P W 11549 /1737/I
No

Enclosure No

PI SECRET T
3129
Date 16/1/42

Subject - Treatment of tanks in and around Mysore City for Anti-Malaria purposes

Sir,

With reference to your reminder No P W 4248/S dated 5/12/1941 on the above subject, I have the honour to inform you that the detailed reports called for from the Superintending Engineer, Mysore Circle and the Director of Public Health in Mysore have not yet been received and they have been reminded A reply will be sent to you on receipt of ~~the~~ their replies

I have the honour to be,
Sir,
Your most obedient servant,

V M S

CHIEF ENGINEER OF MYSORE 13/1

Further report awaited will be kept under Rus

Sec. I

R PW 6400/S 17/1/42

R PW 6599

(4)

322

GOVERNMENT OF MYSORE

Telegraphic Address

No 16698
Encls

OFFICE OF
the Chief Engineer of Mysore,
Camp - Arsikere

Date 11th March 1942

To

The Secretary to Government,
Public Works Department,
Bangalore

4287
12/3/42

Sir

Treatment of tanks in and around Mysore City for anti-malaria purposes

---

With reference to your reminder No P W 6400/S dated 19th February 1942 regarding the above subject, I have the honour to inform you that the detailed reports called for from the Superintending Engineer Mysore Circle and the Director of Public Health in Mysore, have not yet been received and they have been reminded again in the matter A reply will be forwarded to you on receipt of the reports

I have the honour to be
Sir,
Your most obedient servant,

6/3/42

Offg Chief Engineer of Mysore

UBLIC WORKS SECRETARIAT

Draft for Approval

No. PW 7425-27

Dated 25/3/1942

Encl

(5)

FROM

The Secretary to Government,
Public Works Department

To

The Chief Engineer of Mysore.
Bangalore.

Subject Treatment of tanks in and around Mysore city for anti-malaria purposes.

Sir,

With reference to your letter No 16698 dated 11 3 1942 intimating that the reports called for from the Superintending Engineer Mysore circle, and the Director of Public Health are still awaited, I am directed to state that, as the question is pending since five months, arrangements may be

WD 01090—GPB—20 000—27 12 40

UBLIC WORKS SECRETARIAT

Draft for Approval

o. PW 7425-27

ated 25/3/1942

ncl

(5)

FROM

The Secretary to Government,
Public Works Department

To

The Chief Engineer of Mysore.
Bangalore

Subject Treatment of tanks in and around Mysore city for anti-malaria purposes-

Sir,

With reference to your letter No 16698 dated 11 3 1942 intimating that the reports called for from the Superintending Engineer Mysore circle, and the Director of Public Health are still awaited I am directed to state that as the question is pending since five months, arrangements may be

WD 01090—GTB—20 000—27 12 40

made to obtain the report from the Superintending Engineer within a fortnight.

I have etc

for Secy to Govt

Copy wpe to the Director of Public Health for information. The report on the subject may kindly be arranged to be expedited

Copy wpe to the Superintending Engineer, Mysore Circle, for information. The report called for by the Chief Engineer may be furnished within a fortnight

for Secy to Govt

425

GOVERNMENT OF MYSORE

(7)

Telegraphic Address

No 17489
Encls

1 copy of report
2 B/P
3

OFFICE OF
The Chief Engineer of Mysore,
Public Works Department,
Bangalore

Date 23rd March 1942

To

The Secretary to Government,
Public Works Department,
Bangalore

4677
28/3/42

Sir,

Treatment of tanks in and around Mysore City, for anti-malaria purposes

With reference to your reminder No P W 6859 dated 7/3/1942, regarding the above subject, I have the honour to forward, for your kind perusal, a copy of the report furnished by the Assistant Engineer, Headquarter Range to the Superintending Engineer, Mysore Circle and to state that I am suggesting to the Director of Public Health also to kindly arrange for a joint inspection with the Superintending Engineer, Mysore Circle and furnish his views in the matter

I have the honour to be,
Sir,
Your most obedient servant,

24/3/42

Offg Chief Engineer of Mysore

V M S

CNR

28/3/42

H H No 1142

(8)

Letter No 1220 dated 3-3-1942 from the Assistant Engineer, Head Quarter Range, Mysore, to the Superintending Engineer, Mysore Circle, Mysore

---

Reference - Treatment of tanks in and around Mysore City for Malarial purposes

---

With reference to your No 8536/1 dated 29-11-1941 forwarding a copy of letter No C 1890 dated 1st November 1941 from Sir Charles Todhunter, Private Secretary to His Highness the Maharaja of Mysore, I have the honour to state that the tanks in question to be treated are (1) Karanji tank, (2) Goblikatte and (3) Mysore Doddakere

An extract of topo sheet showing the tanks with contours marked thereon is herewith submitted

Karanji tank - A long contour channel catching the water from the slopes of the Chamundi Hills, feeds this tank entering the same on the southern side near the waste weir Whenever the tank is full water stagnates to a certain length of the channel thus causing a breeding place for mosquitoes This causes nuisance to the body gaurds sports club and other dwelling houses closeby

To alleviate this trouble, it is observed that the Palace authorities bunded up this channel near the tank so as to prevent stagnation in a portion of this channel A series of piers are constructed to waste weir level and closed with wooden shutters It is learnt that whenever the water level goes down these shutters would be kept open and once the tank is filled up to waste weir level, the gates are closed and the surplus water in the channel is allowed to go by a bye pass to the waste weir halla

As there are other feeders to this tank, it is a question as to why this source of supply should not be entirely cut off This can be achieved by breaking the bund of the

the contour channel in plans marked A B C D A lead off channel from A, down to the bed of Goblikatte as marked on plan will then be needed to effectively drain off water This will also improve the marshy lands between the Goblikatte and the channel A longitudinal section of this contour channel is also enclosed herewith

Goblikatte - This is a small katte which has very little independent catchment and is to mainly depend upon the seepage water It is learnt that is has got an atchkat of 31 acres of garden land belonging to an Inamdar who pays an - assessment of Rs 37-15-0 Drainage of this tank improves the locality to a great extent The seepage channel referred to above may then be continued and joined on to the drain adjoining Bangalore - Niligiri Road near Madhuvana

As regards Doddakere, it has already been drain off but certain works like strengthening bund here and there are required Levelling of the ground to prevent shallow pools of water being formed is essential This will have to be attended to by the Municipality

If the above proposals are acceptable details regarding cost will be worked out and submitted

---

" C O P Y E

For Offg Chief Engineer of Mysore

V M S

(10)

No 12728

OFFICE OF THE SUPERINTENDING ENGINEER,
MYSORE CIRCLE, P W D

Mysore dated 1/4/ 1942

From

THE SUPERINTENDING ENGINEER,
MYSORE CIRCLE MYSORE

To

The Secretary to Government,
Public Works Department,
Bangalore

P W SECRETARIAT
4854
Date 5/4/42
SUBJECT —

Treatment of tanks in and around Mysore City for anti-malarial purposes

---

Sir,

With reference to your memo No 7427 dated 25-3-1942, on the above subject, I have the honour to state that a preliminary report was submitted to the Chief Engineer in this office No 3495 dated the 9th March 1942 and the same is seen to have been forwarded to you by the Chief Engineer in his letter No 17489 dated 25-3-1942 The views of the Director of Health will be reported after the proposed joint inspection

I have the honour to be,
Sir,
Your most obedient servant,

31 3 42
Superintending ~~Engineer,~~
Mysore Circle

K G

Mr C N R
R
14

(11)

GOVERNMENT OF MYSORE

STATE DEPARTMENT OF HEALTH

P W SECRETARIAT 5009

BUREAU OF EPIDEMIOLOGY AND COMMUNICABLE DISEASES

SESHADRI ROAD

No B E 2743

Enc.

Date 14/4/42 Bangalore (S India) dated 4th April 194 2

From

The Director of Public Health
in Mysore, Bangalore

To

The Secretary to Government,
Public Works Department, Bangalore

Sir,

Re Treatment of tanks in and around Mysore City for anti-malaria purposes

With reference to your Memo No.P W 7426 dated 25th March 1942, requesting that a report on the subject may be arranged to be expedited, I have the honour to request you to kindly refer to this office letter No.B E 2578 dated 18th March 1942 addressed to the Chief Engineer of Mysore, Bangalore, (Copy enclosed for your information)

I have the honour to be,
Sir,
Your most obedient servant,

Director of Public Health

WD 01090—GPB—20 000—27 12 40

1514

Re, Treatment of tanks in and around Mysore City
for anti-malaria purposes

With reference to your letter No 12842 dated 6th bruary 1942 requesting to suggest the names of officers o hold a meeting for discussing the above subject and to uggest a place for the meeting etc , I have the honour to ate that a Committee consisting of the following officers ith others co-opted if necessary may be formed to go into he question. The meeting may be held at Mysore as spot inspection would be necessary

1. Sir Charles Todhunter, K C S I ,
2 The Chief Engineer of Mysore
3. The Director of Public Health
4 The Deputy Commissioner, Mysore District
5 The Superintending Engineer, Mysore Circle
6 The Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore

---

"Copy"

Director of Public Health

WD 01090—GPB—20 000—27 12 40

1514

(13) 13

PUBLIC WORKS SECRETARIAT

Draft for Approval

No. P W 8076

Dated 15/4/1942

Encl

From

The Secretary to Government,
Public Works Department,

To

The Chief Engineer of Mysore
Bangalore.

Subject Treatment of tanks in and around Mysore City for anti-Malaria Purposes.

Sir,

With reference to your letter No 17489 dated 25.3.1942, ~~merely~~ forwarding a copy of the report of the Asst Engineer, Head Quarter Range, indicating certain proposals for treatment of tanks in and around Mysore City as an anti-malarial measure, I have the honor to state that this is an

Sno

WD 01090—GPB—20 000—27 12 40

2/1514

important subject and the Superintending Engineer, who in Mysore, should have paid proper attention to the Scheme and submitted definite proposals with the estimated cost, etc, in consultation with the Director of Public Health

2 I request that you will kindly make a joint inspection with the Director of Health and furnish definite proposals with estimates before the end of this month

I have etc.

13/4/42

Secy. Pwd

13/4

13/4 4/4

(15) 4

PUBLIC WORKS SECRETARIAT

Draft for Approval

No. PW 9584

Dated 25/5/42

Encl

From

The Secretary to Government,
Public Works Department,

To

The Chief Engineer of Mysore
Bangalore

Subject Treatment of tanks in and around Mysore city for anti-Malaria purposes

Sir,

I have the honor to invite reference to PWD 8076 dated 15.4.42 on the above subject and to request you to intimate when the detailed proposals called for herein could be expected

I have etc

18/5/42
for Secy PWD

16/5

WD 01090—GPB—20 000—27 12 40

IMMEDIATE

No 2044
ENCLS 1

PUBLIC WORKS ~~SECRETARIAT~~, Department,
Dated Bangalore, 29th July 1942

FROM

The Chief Engineer of Mysore,
~~Secretary to Government,~~
Public Works Department,
Bangalore

590
Date 30/7/42

To

The Secretary to Government,
Public Works Department,
Bangalore

SIR,

Subject - Treatment of tanks in and around Mysore City for antimalarial purposes

With reference to correspondence ending with your reminder No P W 67 dated 6th July 1942, on the above subject, I have the honour to enclose herewith a copy of the letter No B M 149 dated 16th July 1942 from the Director of Public Health in Mysore, embodying the proposals formulated upon joint inspection of the tanks in and around Mysore City by me and the Director of Public Health along with the Superintending Engineer, Mysore Circle and the Sanitary Engineer

As a few of the works are being attended to by the Health Department I propose that the entire proposals may be worked out by them to avoid confusion

I request communication of approval of Government to the proposal

A copy of the Head Quarter Range Assistant Engineer's letter dated 3rd March 1942 mentioned in the present communication of the Director of Public Health was forwarded to you with this office No 17489 dated 25th March 1942

I have the honour to be,
Sir,
Your most obedient servant,

29/7/42
Chief Engineer of Mysore

CNR
30/7

V M S/28th

Letter No B M 149 dated 16th July 1942 from the Director of Public Health in Mysore, Bangalore, to the Chief Engineer of Mysore, Bangalore

---

Re - Treatment of tanks in and around Mysore City for anti-malarial purposes

---

With reference to your No 19903/737/I dated 14th April 1942 and your D O No 32 dated 4th July 1942, requesting me to furnish my views on the proposals made by the - Assistant Engineer, Headquarter Range, Mysore, I have the honour to state that as per joint inspection I had with you in company with the Superintending Engineer, Mysore Circle, and the Sanitary Engineer, Bangalore, the following measures may be adopted -

1 Karanji Tank - As stated by the Assistant Engineer, Headquarter Range, in his letter No 1220 dated 3rd March 1942 to the Superintending Engineer, Mysore Circle, the Palace authorities have already made certain arrangements to divert the water from the contour channel coming at the foot of Chamundi Hills and round the Lucerne Garden and at the back of the Infantry Lines The contour channel is badly silted up and has to be regraded with proper fall after removing the silt At present there are a number of pools all along the contour channel breeding mosquitoes As suggested by the Assistant Engineer, a cut may be made in one or two places to release the channel from holding up of the water It is seen that the land behind the Karanji Tank is water logged and swampy To drain off this area, it is essential to introduce a set of underground clay pipe drains to lead off the water to the lower Dodkere Tank and to keep the whole area entirely dry

2 Goblikere Tank - Work to the extent of Rs 500/- has been undertaken by this Department and to a great extent

the complaint has already been removed Further an estimate for Rs 3,022/- for laying clay pipe drains along the valley is received from the Sanitary Engineer and if this work is taken on hand and completed, the Lucerne Garden valley will be much relieved At the same time a pipe sluice in the deepest portion of Goblikere Tank is proposed to be introduced, which will further deplete the katte, keeping the entire area dry The Assistant Engineer in his letter has stated that there are 31 acres of garden land belonging to an Inamdar who pays an assessment of Rs 37-15-0 The Deputy Commissioner, who was enquired, has intimated that there are no atchkat lands behind the tank and that the same may be depleted As such, there will be no difficulty in introducing the pipe sluice as suggested above and depleting the Tank

As regards the Dodkere Tank, no doubt the tank has been fairly well drained, but the stgnation here and there during rains that is now occurring may completely be brought under control if a system of underground clay pipe drains is introduced along the valley lines, coming from the Mirza Road and from the Lalithamahal and Race Rourse sides If this is put in, the bed could be kept perfectly dry

3 Kukkerehalli Tank - The Sanitary Engineer has already prepared an estimate for draining the area of this tank As suggested by you during joint inspection, an additional longitudinal drain on the upper side of the road running behind the Tank bund and immediately at the toe of the bund will be added on to the estimate as also an additional culvert to lead off the water from this upper jelly drain If this is done, the drainage arrangements would proove to be satisfactory

The above proposals are in accordance with the views formulated during the time of our joint inspection, and necessary further action may be taken and a report may be sent to Government accordingly

---

" C O P Y "

29/7/4

Chief Engineer of Mysore

V II S/28th

19

GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

General and Revenue Secretariat

No G 2785/P.H

Dated, Bangalore, 28th August 1942

FROM

The Secretary to the Government of His Highness the Maharaja of Mysore, Law Department

To

The Director of Public Health in Mysore
Bangalore

Sir,

With reference to your letter No B M 149 dated 14th July 1942 to the Chief Engineer of Mysore proposing certain measures for treatment of tanks in and round Mysore City for anti-malarial purposes, I am directed to request you to submit to Government in consultation with the Public Works Department definite proposals for consideration within two months from date

The matter may be kindly treated as urgent

I have the honor to be,
Sir,
Your most obedient servant,

Sd/ G Narayanaswamy Naidu
Secretary to Government,
Law Department

Memo No G. 2786 Dated Bangalore the 28th August 1942

Copy of the above is forwarded with compliments to the Chief Engineer of Mysore, for information with reference to his letter No 2044 dated 29th July 1942 to the Secretary to Government Public Works Department

for Secretary to Government,
Law Department

20

Appendix F G—1]

SUBJECT Treatment of tanks in and around Mysore City for anti malarial purposes

3 Spes

Section PH

File No 46-42

Serial No 1

Diary No of letter replied to

No G 2785

To

The Director of public Health in Mysore Bangalore

General and Revenue Secretariat

( )

the 19

Date of issue 28/8/42

Signed by Mr C S S.C

Sir,

With reference to your letter No B M 149 dated 14 7 1942 to the Chief Engineer of Mysore proposing certain measures for treatment of tanks in and around Mysore City for anti malarial purposes I am directed to request you to submit to Govt in consultation with the public works Department definite proposals ~~to Government~~ for consideration within two months from ~~the~~ date ~~the~~

List of enclosures

Copied by

Examined by

P 70

The matter may be thereafter treated as urgent

I have etc

for Secretary to Govt
Land Dept

27 8.42

Memo No G 2756

Copy of the above is forwarded with compliments to the Chief Engineer of Mysore for information with reference to his letter No 20414 d 29 7 42 to the Secretary to Govt P & C D

for Secretary to Govt
Land Dept

Copy to P & C Sec

27/8

22

Appendix F G—1]

SUBJECT

Section PH

File No 46-42

Serial No

Diary No of letter replied to

Reminder

D.O. No G. 5452

To The director of Public Health in Mysore

General and Revenue Secretariat

( )

the 19

Dear Sir,

I am desired to invite reference to this office letter No G. 2785/PH 46-42-1 07 28-8-1942 calling for definite proposals in connection with the treatment of tanks in and around Mysore City for anti-malarial purposes within two months time from 28-8-42 and to request you to send the said proposals immediately

Yours sincerely

Date of issue 31.10.42

Signed by Mr K R S

List of enclosures

Copied by 31/X/42

Examined by

WD 086—GPB—40 000—30 7 40

(Please type or write here)

D O No 958

P PARTHASARATHY Esq LMS BSSc
LRCP LRC DTM DPH
Director of Public Health

Office of the Director of Public Health
in Mysore,
BANGALORE

Dated 2nd November 1942

Dear Sir,

Reference to your letter No.G.5452/P.H. dated 31-10-1942, I desire to state that the preliminery report and the estimates were received by about 20th of October while I was in Mysore during the Dasara Session I have checked the estimates and the scheme and given further instructions As certain modifications have to be effected in the drawings and estimates, the submission of the scheme will be delayed. I shall be able to send the scheme by about the end of this month

Yours sincerely,

P Parthasarathy

C Narayana Swamy Naidu, Esq. B A , B.L.,
Secretary to Government,
Law Department,
Bangalore

NR.2 11.

DEPARTMENT OF PUBLIC HEALTH.

No.B.M. 1639

Office of the Director of Public Health,
in Mysore, Bangalore, date, 30-1-1943.

To

The Secretary to Government,
Law Department,
Bangalore

SUB: Comprehensive estimate amounting to Rs. 49,800/- for treatment of tanks and water courses in and around Mysore City for antimalaria purposes.

Sir,

In continuation of this office letter No. B.M. 1454 dated 8/9th January 1943 intimating that the estimate for the treatment of Tanks in and around Mysore City has been forwarded to the Chief Engineer etc., I have the honour to state that the Chief Engineer after scrutiny, has agreed with the proposals mady by this office. I am enclosing herewith the detailed estimates with plans for information of Government and request you to be so good as to obtain and convey orders of Government, so that the works may be taken on hand early.

I have the honour to be
Sir,
Your most obedient servant
DIRECTOR OF PUBLIC HEALTH.

MSSR.

6479/L

Gm 6182

WD 07011—GPB—75 000—26 5 42

C I No 40]

194

From

The Director of Public Health
in Mysore, Bangalore.

To

The Secretary to Government
Law Department,
Bangalore

Dated April 21, 1943

Despatched

Received

General No Bm 2335

No

Enclosure No one Report
one estimate
one Plan

Sub - Treatment of tanks and water courses in and around Mysore City for anti malaria purposes.

Sir,

In continuation of this office letter No.B.M.1639 dated 1-2-1943 requesting to convey sanction of Government to an estimate amounting to Rs 49,800/- for the above works I have the honour to enclose herewith another estimate for Rs 2,500/- for breaching Basappana Katte behind Saraswathi Puram, Mysore and to state that the Chief Engineer after scrutiny has agreed with the proposals I request you to be so good as to obtain and convey orders of Government in the matter at your early convenience

I have the honour to be,
Sir,
Your most obedient servant,

Director of Public Health.

GEN & REV SECRETARIAT 6479/L

GEN & REV SCOTT 24 APR 1943

25

Appendix F G —1]

SUBJECT

Section Ml

File No

Serial No

Diary No of letter replied to

No L/10441

General and Revenue Secretariat

( )

the *194*

To

The Pdt, adj ml cl, Mysore

Sir,

Date of issue 24/4

I am directed to forward hereworth in original the plans and estimates ~~and plans together with the report~~ ~~amounting to~~ for Rs 49,800 together with a report [illegible] for the treatment of tanks and water courses in and around Mysore city for anti-malaria purposes ~~received from the Dr of Health~~ and to request you to be so good as to consider the question, in consultation with the Ml cl and the city Improvement Trust Board, Mysore, and to submit definite

Signed by Mr. C.R. Rao

List of enclosures

Codied by

Examined by

and presented with
proposals before the end
of May 1943 for the orders
~~Consideration of Govt~~ — 2 The plans & estimates may be kept of return with your reply

I have etc
for
Dr Secy to Govt
W.B. Rao Dept
17/4

L 10691 4/5 (27)

To The Secy, City Mnl Cl, Mysore.

Sir, ~~I have the~~ In continuation of this office letter No L 10441 dt 24-4-43 forwarding for consideration by the City Mnl Cl & the Trust Board an estimate for Rs 49,800/- for the treatment of tanks & water courses in and around the Mysore city for anti-malaria purposes, I am directed to forward herewith, ~~for necessary action~~, in original, a plan & an estimate for Rs 2 500 to gether with a report received from the Dr of P Health for breaching the Basappanakatte behind Saraswathi-puram, Mysore

The enclosures may be kindly returned along with ~~your~~ the proposals as already stated

Yours faithfully
for Law Secy to Govt

(28)

This is a matter
dealt with at P-2-4
to which it may be
2/3

Mr KB
P L [illegible]
[illegible]

and practicable —
proposals
of Mr Ay
~~Consider~~

No B.M 1304

Office of the Sup Director of Public Health in Mysore,

Bangalore, Dated 27th February 1945

To

The Secretary to Government,
Education Department, Bangalore

Sir,

Subject - Treatment of tanks and water courses in and around Mysore City for anti-malaria purposes

---

In continuation of this office letters No B M 1639, dated 1-2-1943 and No B M 2335, dated 21-4-1943 submitting the estimates for Rs 49,800/- and 2500/- respectively for the above works, I have the honour to request you to kindly obtain and convey early orders of Government

I have the honour to be,
Sir,
Your most obedient servant,

Director of Public Health

NB

and fresh wine
proposals
in Albany
Consider

No D2 C-85/44-45

Office of the Chairman,
City Improvement Trust Board, Mysore

Dated 8th March 1945

FROM

R. RAMACHANDRA RAO BHOMBORE, Esq , B A ,
THE CHAIRMAN,
City Improvement Trust Board,
Mysore

To

C Narayanaswamy Naidu, Esq , B A , B L ,
Legal Remembrancer & Secretary to the Government of
His Highness the Maharaja of Mysore, Law Department,
Bangalore

Sir,

I have the honour to state that the drain-off channel now existing in the Doddakere tank bed is an unprotected earthen channel except for a small portion at the beginning and that inspite of the maintenance work done year after year water stagnates in the channel through-out its length affording a breeding place for mosquitoes On account of the close proximity of the tank to the Palace it is urgently necessary to carry out permanent improvement works to the drain-off channel to avoid stagnation of water and consequent unhealthiness in the neighbourhood An estimate was therefore prepared in this office for Rs 50,000/- for protecting the main drain-off channel making due provision therein for revetting the sides of the channel and flooring the bed with dressed slabs on a bed of concrete with a central 'U' shaped drain The estimate for Rs 50,000/- was placed before the Board at its Meeting held on 29th November 1944 The Director of Public Health who is one of the Trustees of the Board was present at the Meeting and informed the Members that plans and estimates were ready in his Office for the drainage of Doddakere tank and would be sent to this office for taking action thereon After several D O reminders the Director has replied in his D O letter dated 21st February 1945 (copy enclosed) that estimates for Rs.49,000/- and Rs 2,500/- had been sent to Government in February and in April 1943 and that an un-official reply was also sent in March 1943 The stage at which the question of sanctioning the above estimates stands at present has not been made clear The work requires to be taken up urgently as it involves the health of the Palace and the neighbourhood I therefore request that orders of Government may kindly be obtained re the sanction to the estimates already submitted by the Director of Public Health and communicated to this office at an early

P T O

(31)

date for taking needful action in the matter.

I have the honour to be,
Sir,
Your most obedient servant,

Chairman 8/3/49

HRS

(32)

D O letter No B M 1256 dated 19th/21st February 1945 from the Director of Public Health in Mysore, Bangalore, to the President, City Municipal Council, Mysore

---

With reference to your D O No D2 C-85/44-45 dated 4th December 1944 and subsequent reminders, I write to inform you that the estimates for Rs 49,000/- were submitted to Government with this office letter No B M.1639 dated 1st February 1943 and another estimate for Rs 2,500/- was sent to Government with this office No B M 2335, dated 21st April 1943 Subsequently a reply unofficially was sent with this Office No B M 2132, dated 27th March 1943

" Copy."

HRS/2

Chairman

2-8/3147

17696-7

L-9741 28/3/48 (33)

To The Dcdt, City Mech, Mysore

Sir, I am directed to invite reference to this office letter No L 10441 dt 24-4-43 in the matter of the treatment of tanks and water courses in and around Mysore city for anti-malaria purposes at an estimated cost of Rs 49,800/- and to request you to state in what stage the question stands at present. A very early reply is requested ~~by return of post~~

I have etc

for Secy to Govt
Law Dept

Appendix F G—1]

SUBJECT

(34)

Section

File No

Serial No

Diary No of letter replied to

No L-16057

To MC1

General and Revenue Secretariat

(.)

the 194

The Chairman,
C.D.T. Bd, Mysore

Sir,

Date of issue 7-4-45

with reference to your letter no D2 C85/44-4 D 8-3-45 in the matter of sanctioning an estimate for Rs 49,000/- forwarded by the Dr of P. Health for the Drainage of the Doddakere Tank in the city, I am directed to state that the Bdt, C.D.M.C, Mysore was requested in this office letter no L1044 D 24-4-43 to consider the

Signed by Mr G R Rao

List of enclosures

Copied by

(Copy sent for ready reference) "J"

Examined by

WD 0741—GPB—15,000—30-10-44

(35)

question of the treatment of water courses in Karachi. Mysore, in consultation with the Secy. of the City Improvement Trust Board & to submit definite proposals for the orders of Govt. to the. No reply has been received from him ~~the~~ ~~so far.~~ A reminder ~~was also~~ issued to him on 28-3-45.

A copy of your letter will be sent to him with a request to expedite the proposals called for in this office letter referred to above.

Yours etc
for Law Secy to Govt.

Memo No L 10058 (incl) dt 7.4.45

Copy of the above is forwarded with compliments to the Secy, City Improvement Trust Board, Mysore, together with a copy of the letter No D2 e85/44-45 dt 8.3.45 received from the ~~Secy~~ Chairman, C I T Bd, Mysore, on the subject. He is requested to expedite the proposals called for from him that any further delay.

By Order
for Secy to Govt
Law Dept

No M S 181-622/44-45 — (36)
Encl
From
To

Office of the Pres
City Municipal Council, M,
Date 2nd May 1945
7275

R Ramachandra Rao Bhombore, Esq B A,
President City Municipal Council
MYSORE

C Narayanaswamy Naidu, Esq ,B A ,B L,
Legal Remembrancer and Secretary to Government
Law Department, Bangalore.

Sir,

Subject - Treatment of tanks and water courses in and around Mysore City for anti-malaria purposes

Adverting to your memo No L 10058 dated 7th April, 1945 forwarding a copy of your letter No L 10057 dated 7th April 45, addressed to the Chairman, City Improvement Trust Board, and calling for the opinion of the Council, I have the honour to forward herewith a copy of Council Resolution No 856 dated 27th April 1945 requesting the Trust Board to take up the works early, together with the following enclosures

* Copy of letter dated 30-4-45 addressed to the Chairman, Trust Board, Mysore

2 Copy of the Municipal Engineer's note dated 25-4-45

I have the honour to be,
Sir,
Your most obedient servant,
R Ramachandra Rao
PRESIDENT

SNR

MYSORE CITY MUNICIPALITY.

Proceedings of the Ordinary General Meeting of the Mysore City Municipal Council held on Friday the 27th April 1945, at 4-30 P.M.

PRESENT.

1. R.Ramachandra Rao Bhombore, Esq.,B.A., President.
2. T.Venkataramaniah, Esq., Vice.President.
3. A.Krishnamurthy Rao, Esq.,
4. T.Narasimha Iyengar, Esq.,B.A.,B.L.,
5. A.N.Suryanarayana Rao, Esq.,
6. B.Narayanaswamy, Esq.,B.A.,B.L.,
7. K.S.Satyanarayana Rao, Esq.,
8. T.Mariappa, Esq.,B.A.,LL.B.,
9. G.R.Rangaswamiah, Esq.,
10. M.V.Venkataramiah, Esq.,
11. M.S.Nanjappa, Esq.,
12. H.Thammiah, Esq.,
13. M.R.C.Basappa, Esq.,
14. E.P.Nanjappa, Esq.,
15. V.N.Dasappa, Esq.,
16. Patna, Srinivasa Setty, Esq.,
17. F.C.Devaraj Urs, Esq.,
18. Mrs.W.H.Theobald,
19. K.Siddiah, Esq.,
20. T.S.Ali Khan, Esq.,

ABSENT.

21. P.Sitharamiah, Esq.,B.A.,B.L.,
22. M.N.Jois, Esq.,B.A.,
23. Agaram Ranginh, Esq.,
24. T.S.Chandrasekhara Gowda, Esq.,
25. U.L.Ramachandra Rao,Esq.,
26. Chowdiah, Esq.,
27. Dr.A.V.Ranga Rao.
28. Gulam Ahamed Khan, Esq.,
29. Mohamad Sait, Esq.,
30. G.Janardan Naidu, Esq.,
31. Vacant.

---

856 Letter No L 10058 dated 7-4-1945 from the Secretary to Government, Law Department, calling for opinion in the matter of sanctioning an estimate for Rs 49,000/- forwarded by the Director of Public Health for the treatment of tanks and water courses in and around the Mysore City for anti-malaria purposes, and Municipal Engineer's note dated 25-4-1945

The Council approves of the note and requests the Trust Board to kindly take up the works early

Sd R Ramachandra Rao Bhombore,
President

"COPY"

R [signature]
PRESIDENT

snr

38

Letter No. [illegible] / dated 30-4-45 from the President, City Municipal Council, Mysore, to the Chairman, City Improvement Trust Board, Mysore

---

Subject - Treatment of tanks and water courses in and around Mysore City for anti-malaria purpose:

Adverting to your letter No D2-C 85/44-45 dated 8th March 45 addressed to Government, a copy of which has been forwarded to this office, for the opinion of the Council, I have the honour to state that the subject was discussed at the Ordinary General Meeting of the Municipal Council, held on 27th April 1945, along with the note prepared by the Municipal Engineer, enclosing a revised estimate for Rs 1,40,000 as against the original estimate for Rs 49,800/- prepared in the year 1942 The Municipal Council have approved of the Municipal Engineer's note dated 25th April,45 and resolved to request the Trust Board, kindly to take up the works early

A copy of the resolution No 856 dated 27th April 1945 together with a copy of the Engineer's note and copy of the revised estimate, are enclosed for favour of necessary further action in the matter The connected file of the Trust Board office, is also returned herewith

---

"COPY"

PRESIDENT

SNR

Note on the estimate amounting to Rs 1,40,000/- for treatment of tanks in and around Mysore City for Anti-malarial purposes

---

On a reference from the Secretary to Government, Law Department to the Director of Public Health in Mysore, Bangalore (vide letter No G 2785/PH 46-42-1 dated 20th August 1942) the Director of Public Health prepared an estimate amounting to Rs 49,800/- for the above purposes and submitted it to Government in 1943 Government in their letter No L 10441 dated 24-4-43 referred the estimates to the President, City Municipal Council, Mysore, requesting the President, to consider the question in consultation with the Municipal Council and City Improvement Trust Board, Mysore and to submit definite and practical proposals The several tanks and water courses proposed to be dealt with and the amount of the estimates are as per statement herein enclosed

The main item of work consists of sectioning the hallas, filling up cess pools and draining away the marshy areas - sub-soil drainage to be effected by laying perforated burnt clay pipes and also jelly drains The estimate originally prepared for Rs 49,800/- is now revised and works out to Rs 1,32,000 ~~is now revised and~~ as per current rates To this, an amount of Rs 8,000/- is added in the shape of Establishment and petty supervision charges as this is a large work necessitating special staff The report accompanying the estimate and the drawings and detailed estimates give the items of work that are proposed to be carried out in each area It is a point for consideration as to the source of meeting the cost of the entire project since this is a work requiring very heavy outlay and considering the meagre finances of the Municipality it is proposed to request Government to meet this cost entirely out of Trust Board funds and make over the entire system to the Municipality for maintenance

Sd H Sundaravaradachar,
Municipal Engineer

"COPY"

PRESIDENT

SNR

Statement showing the items of work, amount of original estimate and amount of Revised estimate, relating to the treatment of tanks in and around Mysore city for Anti Malarial purposes.

Sl. No.	Items of work.	Original Est.	Revised Est.	Remarks
1.	Sub-soil drainage to area in the rear of Kukkarahalli Tank	5700/-	14,055/-	
2.	Improving feeder channel to Karanjikere	3100/-	7,635/-	
3	Sub-soil drainage to Lucerene garden	3630/-	11,975/-	
4	Sub-soil drainage to Goblikere Tank ~~bundx~~ Bed.	8320/-	18,450/-	
5	Sub-soil drainage to the area in the rear of Karanji ~~tank~~ kere.	3350/-	10,375/-	
6	Sub-soil drainage to Doddakere tank bed.	10000/-	32,375/-	
7.	Sub-soil drainage to Halladakeri including Wellington Lodge premises.	15700/-	36,270/-	
	Total -	Rs. 49800/-	Rs 1,31,135/-	
	Grand Total -	-	Rs 1,32000/-	
	Add for establishment		8000	
		Total	140,000	

TPS.

K Sundaramachar
Municipal Engineer,
Mysore
2/5/4

Appendix F G —1]

SUBJECT

Diary No of letter replied to

General and Revenue Secretariat

( )

the 194

Date of issue 17/5/45

Signed by M S R Rao

List of enclosures

Copied by

Examined by

Section

File No

Serial No

No L-11171

To

The Chairman,
C & T Bd, Mysore

Sir,-

With reference to the correspondence ending with your letter No MS 181-622/44-45 dt 2-5-45 re the treatment of tanks and water courses in & around Mysore city for anti-malaria purposes, I am directed to request you to furnish information on the following points —

(1) Is the work referred to by you in your letter dated the 8th March 1945 included among the several items, the list of which has been sent to the Govt

WD 0744—GPL—15,000—30 10 44

2. If so which is it? &

NB Is it not a separate item?

Yours etc
[illegible]
For say to Cart
NB. [illegible] Sept 18

URGENT

43

No D2 C 85/44-45 (Enclos9)

Office of the Chairman,
City Improvement Trust Board, Mysore

Dated 11th August 1945

GEN & REV SECRETARY
1070
13 AUG 1945
L S & BRANCH

FROM

R RAMACHANDRA RAO BHOMBORE, Esq , B A ,
THE CHAIRMAN,
City Improvement Trust Board,
Mysore

ADDITIONAL SECRETARY
No
L e 1316
GOVERNMENT OF MYSORE

To

B Mallaradhya, Esq , M A ,
Additional Secretary to the Government of
His Highness the Maharaja of Mysore, Bangalore

Sir,

Subject - Re treatment of tanks and water courses in and around Mysore City for anti-malarial purposes

In forwarding herewith an estimate amounting to Rs 1,40,000/- together with the accompanying Report and the Board's Resolution dated 21st June 1945, I have the honour to state that the incidence of malaria in the City has in recent years increased owing to the stagnation of water in pools along the water courses in and around the City The Dewan Sahib was pleased to inspect the several localities referred to in the scheme on 1st August 1945 in company with the Sanitary Engineer and the undersigned and was pleased to order that this work may be taken up immediately as the localities had become a breeding place for mosquitoes, particularly in the neighbourhood of the Palace

2 Under the above circumstances, I request that sanction of Government may kindly be obtained to the estimate and for getting the scheme worked out by the Sanitary Department at an early date In this connection, I may state that the above scheme has been worked out by the Director of Public Health The original estimate for Rs 52,300/- has to be revised to Rs 1,40,000 due to enhanced schedule rates

3 The plans prepared by the Sanitary Department accompany

(Vide Law Secretary's letter no 10691 dated 1-5-1943 to the President, City Improvement Board, Mysore)

I have the honour to be,
Sir,
Your most obedient servant,

Chairman

IRS

1419/45

1070/2

44

R. Ramachandra Rao Bhombore 2/18
CHAIRMAN

CITY IMPROVEMENT TRUST BOARD
MYSORE

GEN & PER SECRETARIAT 1618 5 SEP 1945 L S & BRANCH

D O No D2 C-85/44-45 1st September 1945

DEWAN 3 SEPT 1945 706/45-46

Dear Mr Narasimha Moorty,

Re Treatment of tanks and water courses in and around Mysore City for anti-malarial purposes

I write to inform you that an estimate amounting to Rs 1,40,000/- for the work referred to above was submitted to the Additional Secretary with this office No D2 C-85/44-45 dated 9th August 1945, under instructions from the Dewan Sahib who was pleased to inspect the several localities referred to in the scheme on 1st August 1945 A copy of the same is enclosed herewith

The estimate etc , submitted to the Additional Secretary may kindly be obtained from him and placed before the Dewan Sahib as instructed by him on 29th August 1945

Yours sincerely,

R. Ramachandra Rao

C Narasimha Moorty, Esq , B A ,
Private Secretary to the Dewan,
Bangalore

Where is this held up? 3/9

Submitted for orders
3/9/45

May be expedited
3/9/45
3/9

Urgent.

45

Letter No D2 C 85/44-45, dated 9th August 1945 from the Chairman, City Improvement Trust Board, Mysore, to the Additional Secretary to the Government of His Highness the Maharaja of Mysore, Bangalore

---

Subject.- Re treatment of tanks and water courses in and around Mysore City for anti-malarial purposes

---

In forwarding herewith an estimate amounting to Rs 1,40,000 together with the accompanying report and the Board's Resolution dated 21st June 1945, I have the honour to state that the incidence of malaria in the City has in recent years increased owing to the stagnation of water in pools along the water courses in and around the City The Dewan Saib was pleased to inspect the several localities referred to in the scheme on 1st August 1945 in company with the Sanitary Engineer and the undersigned and was pleased to order that this work may be taken up immediately as the localities had become a breeding place for mosquitoes, particularly in the neighbourhood of the Palace

Under the above circumstances, I request that sanction of Government may kindly be obtained to the estimate and for getting the scheme worked out by the Sanitary Department at an early date In this connection, I may state that the above scheme has been worked out by the Director of Public Health The original estimate for Rs 52,300/- (vide Law Secretary's letter No 10691 dated 1st May 1943, to the President, City Municipal Council) has to be revised to Rs 1,40,000/- due to enhanced schedule rates

The plans prepared by the Sanitary Department accompany

" Copy "

R Nagaraj

Chairman

HRL.

46

R. Ramachandra Rao Bhombore
CHAIRMAN

GEN & ... 653 ... 1945 ... BRANCH

CITY IMPROVEMENT TRUST BOARD
MYSORE

D.O.No. D2.C-85/44-45 ... 1st September 1945.

Dear Mr Narasimha Moorty,

Re: Treatment of tanks and water courses in and around Mysore City for anti-malarial purposes

I write to inform you that an estimate amounting to Rs 1,40,000/- for the work referred to above was submitted to the Additional Secretary with this office No D2 C-85/44-45 dated 9th August 1945, under instructions from the Dewan Sahib who was pleased to inspect the several localities referred to in the scheme on 1st August 1945 A copy of the same is enclosed herewith.

The estimate etc., submitted to the Additional Secretary may kindly be obtained from him and placed before the Dewan Sahib as instructed by him on 29th August 1945

Yours sincerely,

(Sd) R Ramachandra Rao Bhombore

ADDITIONAL SECRETARY
3/9

C.Narasimha Moorty, Esq, B A,
Private Secretary to the Dewan,
Bangalore

D2 C 85/44-45

Copy ~~submitted~~ forwarded with compliments to the Additional Secretary to the Government of His Highness the Maharaja of Mysore, Bangalore, with reference to this office No D2 C 85/44-45 dated 9-8-1945

Chairman

GOVERNMENT OF HIS HIGHNESS THE MAHARAJA ~~OF~~ 48 MYSORE

No L-2029

General and Revenue Secretariat

Dated Bangalore 14/9/45

From

The Additional Secretary to the Government of His Highness the Maharaja of Mysore
Law Department

To

The Chairman,
City Improvement Trust Board, Mysore.

Sir,

Sub.- Treatment of tanks and water courses in and around Mysore City, for anti-malaria purposes.

- - -

With reference to the correspondence ending with your letter No.T.I.C.85/44-45 dated 11-8-45, forwarding for sanction, an abstract estimate for Rs.1,40,000/- for the above work, I am directed to state that detailed estimates for the works - if they have been prepared may be kindly arranged to be forwarded, immediately.

The enclosures are herewith returned.

I have the honour to be,
Sir,
Your most obedient servant,

G B Mallanadhya
Sd. ~~G. Ramachandra Rao.~~
~~For~~ Additional Secretary.

14/9/45

No L 2030

Copy with compliments to the Director of Public Health in Mysore, for information and early necessary action.

By Order,

For Additional Secretary.

Extra Copy

GRD.

[illegible]

49

GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

No R 2029

General and Revenue Secretariat

Dated Bangalore 14/9/45

From

The Additional Secretary to the Government of His Highness the Maharaja of Mysore
Law Department

To

The Chairman,
City Improvement Trust Board, Mysore.

Sir,

Sub.- Treatment of tanks and water courses in and around Mysore City, for anti-malaria purposes

- - -

With reference to the correspondence ending with your letter No.D.2 C.85/44-15 dated 11-8-45, forwarding for sanction, an abstract estimate for Rs.1,40,000/- for the above work, I am directed to state that detailed estimates for the works - if they have been prepared may be kindly arranged to be forwarded, immediately.

The enclosures are hereunto returned.

I have the honour to be,
Sir,
Your most obedient servant,

Sd. G. Ramachandra Rao
For Additional Secretary.

P L-2030

14/9/45

Copy with compliments to the Director of Public Health in Mysore, for information and early necessary action.

By Order,

For Additional Secretary.

GRD.

No L-2029 Immediate 14/9/45

MR

To The Chairman C & T Board Mysore 47

Treatment of tanks and water courses in and around Mysore city, for anti-malaria purposes

With reference to the correspondence ending with your letter no D 2-C 85/44-45, D 11-8-45, forwarding for sanction an abstract estimate for Rs 1,40,000/ for the above work, I am directed to state

That detailed estimates for the works - if they have been prepared - may be kindly arranged to be forwarded, immediately

The enclosures are hereunto returned

Yours &c
for Addl Secy

No. L 2030, 14/9/45

Copy w.c. to the Director of P.&A. in response, per inform. & early necessary action

B.O.
for Addl Secy.

No D2 C-85/44-45

Office of the Chairman,
City Improvement Trust Board, Mysore

Dated 28th Septr. *194* 5

FROM

R RAMACHANDRA RAO BHOMBORE, Esq , B.A.,
CHAIRMAN,
City Improvement Trust Board,
Mysore

J. B. Mallaradhya, Esq., M.A.,
Additional Secretary to the
Government of His Highness the
Maharaja of Mysore, Bangalore.

Sir,

Subject:- Treatment of tanks and water courses in and around Mysore City, for anti-malarial purposes

With reference to your letter No.L 2029 dated 14th September 194 directing that the detailed estimates for the above work, if they have been prepared, may be kindly arranged to be forwarded to Government etc., I have the honour to state that the scheme was prepared by the Public Health Department and sent here for obtaining sanction of the Trust Board and providing for necessary funds There is no trained staff in the Trust Board Office to take up the work of preparing detailed estimates and as the work is going to be executed by the Public Health Department, I request that the detailed estimates may be prepared by them.

I have the honour to be,

Sir,

Your most obedient servant,

Chairman.

HRS.

No L 3248 (51) 22/10/45

To The Director of Public Health in Mysore

Treatment of tanks and water courses in and around Mysore city for anti-malaria purposes

Sir,

I am directed to invite reference to his office memo No L 2030, dated 14-9-45, and to request that the detailed estimate for the above work may be prepared and submitted to Govt very early

I have the

MOR

for Addl Secy 18/10

(52)

71/45-46

16/11

Office of the Director of Public Health in Mysore,

Bangalore, Dated 14th November 1945

FIN & REV SECRETARIAT 35278 22 NOV 1945 BRANCH

To

The Additional Secretary to Government,
Bangalore

Sir,

Subject - Treatment of tanks and water courses in and around Mysore City for anti-malaria purposes

---

17/11

With reference to your letter No L 3248, dated 22-10-1945, requesting to get the detailed estimates for the above works, prepared and sent to Government etc, I have the honour to state that the estimates submitted to Government were called for, from the Chairman, City Improvement Trust Board, Mysore City, with this office No B M 465, dated 3-10-1945 He has since sent the estimates without the original sent from this office to Government He has been requested to send the original estimate The detailed estimates will be submitted on receipt of the original from the Chairman, City Improvement Trust Board, Mysore

Further, I request you to kindly return the estimate for anti-malaria works in Saraswathipuram area for Rs 2,500/- sent with this office No B M 2335, dated 21-4-1943 if the same has not already been sent to the Chairman, City Improvement Trust Board, Mysore City

I have the honour to be,
Sir,
Your most obedient servant,

Director of Public Health

(53)

3327
19-11-45

No D2.C-85/44-45./Encls.2.

OFFICE OF THE CHAIRMAN
CITY IMPROVEMENT TRUST BOARD MYSORE,
Dated 6th November 1945

FROM

THE CHAIRMAN,
City Improvement Trust Board
Mysore

To

The Director of Public Health in Mysore,
Bangalore.

ADDITIONAL SECRETARY No 12/11

Sir,

Re:- Treatment of Tanks and water courses in and around Mysore City for anti-malarial purposes.

1) With reference to your letter No P M.465 dated 3rd October 1945 on the above subject, I have the honour to enclose herewith copy of this office No D2 C 85/44-45 dated 11th August 1945 addressed to the Additional Secretary to Government as desired by you

In his No L 10691 dated 1st May 1943 the Secretary to Government Law Department forwarded to this office an estimate for Rs 49,000/- prepared by the Sanitary Engineer, Bureau of Sanitary Engineering for the above work for consideration of the Municipal Council and the Trust Board This estimate seems to have been prepared in the Sanitary Engineer's Office on 14th December 1942.

This estimate is seem to have been subsequently revised in this office by noting the rates prevailing during July 1945 Only the rates have been corrected, without affecting the quantities noted by the Sanitary Engineer in the estimate prepared by him The estimate has swelled to Rs 1,40,000/- (Rs.1,32,000/- for works plus Rs 8,000/- for establishment) It is this abstract estimate that has been submitted to Government with this office No D2 C 85/44-45 dated 11th August 1945.

A copy of the above detailed estimate amounting to Rs.1,40,000/- together with plans is herein enclosed for kind perusal and further necessary action

I have the honour to be,
Sir,
Your most obedient servant,

(Sd) R Ramachandra Rao Bhombore
Chairman

P T.O

Copy of the foregoing is forwarded with compliments to the Additional Secretary to Government, for favour of information, in continuation of this office No D2 4-85/44-45 dated 28-9-1945

R [illegible]
Chairman

HRS

L 475 G 7-12-45

55

To The Director of Public Health

Subj - Treatment of tanks and water courses in and around Mysore city, for anti-malaria purposes

Sir,

With reference to your letter No B M 671/45-46 dated 24-11-45, on the above subject I am directed to state that it is seen that the original Estimate for the above works has been sent to you by the Chairman, E & T. Board, Mysore, with his letter No D 2 C 85/44-45 dated 9-11-45. The detailed Estimate

the works may therefore be sanctioned to Govt early

addl cont

2) The estimate for anti-malaria works in Saraswathipuram area for Rs 2500/ was sent to the Chairman, C & T Board, Mysore with this office letter no L 1069 dt 1-5-45, and the same may be obtained from him, if necessary

HRS

Yours &c
[illegible]
for Revenue Secy

Memo No L4760d 7-12-45

Copy we to the Chairman, C & T Board, Mysore, for information, with reference to his memo no D2-C85 dt 4-11-45

By order
[illegible]
for Revenue Secy

No D2 C-85/44-45.

4272

OFFICE OF THE CHAIRMAN
CITY IMPROVEMENT TRUST BOARD MYSORE

Dated 8th December 1945

FROM

R RAMACHANDRA RAO BHOMBORE, Esq, B A,
CHAIRMAN,
City Improvement Trust Board
Mysore

To

J B. Mallaradhya, Esq, M A,
Secretary to the Government of His Highness the
Maharaja of Mysore, Revenue Department, Bangalore

Sir,

Ref:- Treatment of tanks and water courses in and around Mysore City for antimalarial purposes

---

With reference to your No L 4760 dated 7-12-1945 forwarding a copy of letter No L.4759 dated 7-12-1945 addressed to the Director of Public Health on the above subject, I have the honour to state that the detailed estimate for Rs.1,40,000/- for the above work as well as that for Rs.2,500/- pertaining to anti-malarial works in Saraswathipuram have been already sent to the Director of Public Health with this office No D2 C-85/44-45 dated 29th November 1945 The receipt of these documents have also been acknowledged by him in his No 759 dated 4-12-1945.

I have the honour to be,
Sir,
Your most obedient servant,

R. Ramachandra Rao
Chairman

HRS

gditio,
contint

HRS

For information, with reference to his memo no D2-C85 of 4-11-45

BD

Dev Reve Sey

(58) L 6601 Public Health

To The ~~Chairman, C.S.T. Board,~~ Mysore

~~Mysore~~ Mysore

Subj - Treatment of tanks and water courses in and around Mysore city for anti malaria purposes

Sir,

With reference to the correspondence ending with this office memo No. 4757 dt 7-12-45, on the above subject, I am directed to state that the Chairman, C.S.T. Board, Mysore, has since reported that the Estimate for the above work and the Estimate for anti-malaria works in Saraswathipuram, Mysore City, were

Co

additions

continued

HRS

(59)

Sent you on 29-11-45

I am to request you to forward the detailed estimate called for in this office letter No L 3248 dated 22-10-45, for the above work, very early

Yours faithfully

for Rev Secy

(60)

No B.M. 979

Office of the Director of Public Health in Mysore,

Bangalore, Dated 9th January 1946.

To

The Secretary to Government,
Revenue Department, Bangalore

REV SECRET 4810 15 JAN 1946 LSG BRANCH

Sir,

With reference to your letter No.L 4759, dated 7th December 1945, I have the honour to state that the Chairman, City Improvement Trust Board, Mysore City, has sent with his letter No D2 C 85/44-45, dated 11th December 1945, the original estimate prepared by the Sanitary Engineer, Bureau of Sanitary Engineering for treatment of tanks and water courses in and around Mysore City for anti-malarial purposes The original estimate prepared by the Sanitary Engineer was for Rs 49,800/ plus Rs 2,500/- for the Saraswathipura area This estimate appears to have been revised in the office of the President, Municipal Council, Mysore City, and the revised estimate as sent amounts to Rs 1,40,000/-. The basis on which the revision was made has not been intimated to this office nor any of the details Under the circumstances, the President, Municipal Council, Mysore City, may be requested to forward the data on which the original estimate was revised, to this office, for scrutiny by the Sanitary Engineer with reference to the original estimate prepared by him The Sanitary Engineer will be requested to scrutinize the revised estimate on the basis of data furnished and return the detailed estimate as revised with his observations for submission to Government

I have the honour to be,
Sir,
Your most obedient servant,

Director of Public Health.

PAPERS FOR DISCUSSION WITH THE MINISTER ON 16-1-1946

(Grants required for the year 1945-46)

Estimate	Amount	Remarks.
1 Estimate for shifting of Kurubarahally-Village	70,000/-	T O No 128/45-46 dated 22-11-45 to the Additional Secretary
2 Treatment of Water-courses and ways	(1,40,000+ 2500)	D2 C-85/44-45 dated 29-11-45 to the Director of Public Health (Vide T O No D2 C-85/44-45 dated 8-12-45 to the Revenue Secretary
3 New Procession Route	(85000 + 15000=1,00,000)	D2 C-13/44-45 dated 20-11-45 and D2 C-13/44-45 dated 12-1-1946

D 14886/46

15/1/46 Submits the above three files + one [illegible] file = total 4 files

ASG for orders

order to issue memorandum on each item

Dewan's orders on Borough Tree Board form

16/1/46

The above three files are put up

Re item No I, the opinion of the Revenue Commr on the proposal is not yet received + a D-O reminder was issued on 31-12-45

Re item No II The Director of Public Health has not yet furnished the detailed Estimates for the work. D-O reminder issued

Re item No III The detailed Estimate was received early today and is being sent to E-C's Rd for scrutiny

For orders

16/1/46

17/1/46

Two draft D.O.s re. items 1 & 2 are put up

The file re. item no 3 has been sent to the Chief Engineer for R&B for scrutiny and return.

Sd/-
17/1

Sd/-
17/1/66

Jointly signed by Secy

L 6923 d 18-1-66

(63) L. 6923

Immediate - 15-1-46

3

G R S App F G 3

GENERAL AND REVENUE SECRETARIAT

(*Continuation sheet draft form*)

Subj Treatment of tanks and water courses in and around Mysore city for anti-malaria purposes

Dear Sir,

With reference to the correspondence ending with your letter No 979 dated 9-1-1946, on the above subject I am desired to state that all the technical details required by you may be kindly arranged to be obtained directly from the President, City M C Mysore and the detailed estimate for the above work already called for in this office letter No L 3246 dated 22-10-45, may be submitted to Govt within a week

This is an important

WD 0565—GPB—22 500—8 11 38

question which requires expeditious disposal at every stage and personal attention may be kindly bestowed towards its disposal without further delay

Yours sincerely
for

17/1/46

The Director of
Public Health
(By Name)

Memo No. 6924 D 18-1-46

Copy to the Chairman
C U T Board, Mysore.
(with a copy of letter, no.
BM-929 dated 9-1-46 from
the Director of P. Health) with a
request that the information
referred to therein may be
furnished immediately to the
Director of Public Health
in Mysore City.

B...
for
17/1/46
For Secretary

(65)

OFFICE OF THE CHAIRMAN
CITY IMPROVEMENT TRUST BOARD MYSORE,

No D2-C.85/44-45-

Dated 31st January 1946.
1/2/46

FROM

THE CHAIRMAN,
City Improvement Trust Board

To
The Director of Public Health in Mysore, Bangalore
Mysore

Re Treatment of Tanks and water courses in and around Mysore City for anti malarial purposes.

Sir,

With reference to your letter No BM 979 dated 9th January 1946 addressed to the Secretary to Government, Revenue Department, on the above subject, I have the honour to inform you that reasons for the original estimate forwarded by the Sanitary Engineer for Rs 49,800/- having been revised in this office to Rs.1,40,000/- have already been furnished to you in this office No.D2-C-85/44-45 dated 9th November 1945. As explained therein only the rates for several items of the estimate prepared by the Sanitary Engineer as far back as 1942, have been revised in accordance with the rates prevalent during 1945, the quantities having been left unaltered. Hence the original estimate for Rs.49,800/- swelled to Rs.1,40,000/-.

What further details are required now as referred to in your letter dated 9th January 1946 to the Revenue Secretary, may kindly be intimated.

I have the honour to be,
Sir,
Your most obedient servant,
(Sd) R RAMACHANDRA RAO BHOMBORE,
CHAIRMAN.

VNP D2 C85/44-45
1/2/46

Copy of the above is forwarded with compliments to the Secretary to Government, Revenue Department, Bangalore, for reference with reference to his D O No L6923 dated 18th January 1946

CHAIRMAN
31/1

VNP

IMMEDIATE

GOVERNMENT OF MYSORE

(67)

DEPARTMENT OF PUBLIC HEALTH

Rajasevasakta
P PARTHASARATHY L M S B S SC
LRCP LRCS DTM DPH
DIRECTOR OF PUBLIC HEALTH

TELEPHONE No 2144
TELEGRAM HEALTH

~~SUPERINTENDENT~~

BUREAU OF MALARIOLOGY
SESHADRI ROAD

No B M 1163
Encl (12)

Bangalore (S India) dated February 7, 1946

To
The Secretary to Government,
Revenue Department,
Bangalore

SEC. TO GOV. SECRET.
5500
9 FEB 1946
MALARIA BRANCH

Sir,

Subject - Treatment of tanks and water courses in and around Mysore City, for antimalaria purposes

---

With reference to your letter No L 4759 dated 7-12-1945 and subsequent reminders thereon, I have the honour to return 11 Sheets of detailed estimates as revised by the Chairman, City Improvement Trust Board and certified by the Sanitary Engineer I am enclosing for reference of Government a copy of the report of the Sanitary Engineer after verification The delay in forwarding these estimates was unavoidable as the estimates had to be sent to the Sanitary Engineer for verification and return

I have the honour to be
Sir
Your most obedient servant

DIRECTOR OF PUBLIC HEALTH

Letter No 1516 dated 1-2-1946 from the Sanitary Engineer, Bureau of Sanitary Engineering Bangalore to the Superintendent, Bureau of Malariology, Bangalore

---

Re - Comprehensive treatment of tanks in and around Mysore City for antimalaria works

---

With reference to your letter No 1076 dated 22-1-1946, I have the honour to state that the rates provided in the revised estimate by the Trust Board, have been verified with the scheduly of rates of the Municipality and are found to be correct

The rates for the clay pipes and clay collors etc., are also in accordance with the prevailing mareet rates of the locality

The complete file of estimates is herewith returned, which may indly be ac nowledged

---

" C O P Y "

Director of Public Health

(66) Immediate

J. 7833
4.2.46

Dear Sir,

I am desired to invite reference to his Office D.O. letter No L6923, dated 18-1-46, calling for the detailed estimate for the treatment of tanks and water courses in and around Cyprus city, for anti-malaria purposes, within a week and to request that the same may be kindly submitted to you, without any further delay. Might I request you kindly to give urgent attention to this request.

Directly presented by Name Letter

URGENT

No 3 D 2 C 85/44-45

73335 / 23/4/46

(69)

OFFICE OF THE CHAIRMAN
CITY IMPROVEMENT TRUST BOARD MYSORE

Dated 19th April, 46 194

FROM

R RAMACHANDRA RAO BHOMBORE, ESQ ,B A ,
~~THE~~ CHAIRMAN,
City Improvement Trust Board
Mysore

TC 92-45-1

To

J.B Mallaradhya, Esq ,M A ,
Secretary to Government,
Revenue Department,
Bangalore.

Sir,

Subject - Treatment of Tanks and Water Courses in and around Mysore City, for anti-malaria purposes

---

In continuation of this office No FCR 822 dated 29-1-46, forwarding copy of letter addressed to the Director of Public Health in Mysore, regarding the above, I have the honour to request the favour of very early action in the matter, as the subject is very important and urgent

I am to add that the Dewan during his kind inspection of the Mysore City on the 18th inst., was pleased to enquire about the matter and directed that the scheme should be worked without further delay

I have the honour to be,

Sir,

Your most obedient servant,

CHAIRMAN

SNR

(70) 4 L/P&J/12240/1192-245 — 2

Immediate

H R S App F G 3

GENERAL AND REVENUE SECRETARIAT

(*Continuation sheet draft form*).

To

The Chairman, C & T Board
Mysore

Treatment of tanks and water courses in and around Mysore city, for anti-malaria purposes

Sir,

With reference to the correspondence ending with your letter No D & C 85/44-45 dated 19-4-1946, forwarding for sanction an estimate for Rs 1,40,000/ for the above work, I am directed to observe that these estimates were prepared in the year 1942, ~~at and the works were~~ for Rs 49,800- while the present cost of the works is estimated at — — Rs 1,31,000/ (excluding the establishment charges) It is also understood that some of the items of these works have already been

WD 03697—GPB—30 000—2 2 40

partly done by the Trust-Board or by the Health Dept, and that out of the seven works included in the above estimate some of them, are evidently more urgent than the rest. ~~In this view~~

I am accordingly to state that priority should be given to the marginally-noted works These may be taken up first and completed quickly

1) Kukkarahalli tank
2) Doddakere
3) Halladakere Drainage Scheme

The relative estimates may be re-examined and items which have been completed may be deleted --

The works may be carried out by the Trust-Board, with the advice of the Sanitary Engr The estimates are herewith returned for immediate necessary action

I have &c

Revenue Secy to Govt

Estimates

Estimates are sanctioned by Govt subject to necessary alterations, after scrutiny of the revised estimates

Memo No L/12241-2d 4 & 4b

Copy w c to (1) the Director of Public Health in Mysore, for favour of immediate necessary action and the Chief Engineer for information

B-O

for Revenue Secy

(72)

GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

General and Revenue Secretariat

No L 12 240/ml 92-45-2 Dated Bangalore, 4th May 1946.

FROM

The Secretary to the Government of His Highness the Maharaja of Mysore
Revenue Department.

To

The Chairman,
City Improvement Trust Board,
M y s o r e

Subject: Tre tment of tanks and water courses in and around Mysore City, for antimalaria purposes.

***

S i r,

With reference to the correspondence ending with your letter No.DLC.85/44-45 dated the 19th April 1946, forwarding for sanction an estimate for Rs.1,40,000 for the above works, I am directed to observe that these estimates were prepared in the year 1942, for Rs.49,800 while the present cost of the works is estimated at Rs.1,31,000 (excluding the establishment charges). It is also understood that some of the items out of these works have already been partly done by the Trust Board or by the Health Department, and that out of the seven works included in the above estimate some of them are evidently more urgent than the rest.

I am accordingly to state that priority should be given to the marginally noted works These may be taken up first and completed quic ly.

1 Kukkanahalli Tank
2. Doddakere
3 Halladakere Drainage Scheme.

The relative estimates may be re-examined and items which have been completed may be deleted and a revised estimate sent to Government for sanction.

The works in respect of which estimates are sanctioned and necessary grants therefore are allotted after scrutny of the revised estimates may be carried out by the Trust Board, with the advice

of the

of the Sanitary Engineer. The estimates are herewith returned for immediate necessary action.

I have the honour to be,
Sir,
Your most obedient servant,

for Secretary to Government,
Revenue Department.

Spare

Office of the Director of Public Health
in Mysore,
Bangalore, dated 13th May 1946.

To

The Secretary to the Government of
His Highness the Maharaja of Mysore,
Department of Education,
Bangalore

Subject -Treatment of tanks and water courses in and around Mysore City for antimalaria purposes

Sir,

With reference to your memo No L 12241-2, dated 4th May 1946, forwarding a copy of letter addressed to the Chairman, City Improvement Trust Board, Mysore, requesting that immediate action may be taken in the matter etc , I have the honour to state, that this office cannot take any action in the matter, as the Bureau of Sanitary Engineering has since been transferred to the control of the Public Works Department

I have the honour to be,
Sir,
Your most obedient servant

DIRECTOR OF PUBLIC HEALTH

(75)

No.D2.C.85/44-45.

OFFICE OF THE CHAIRMAN,
CITY IMPROVEMENT TRUST BOARD,
MYSORE

Dated 21st May 1946.

GEN & REV SECRETARIAT
28 MAY 1946
8544
L S G BRANCH

From

R. RAMACHANDRA RAO BHOMBORE, Esq , B.A.,
Chairman, City Improvement Trust Board,
Mysore.

To

Rajasevasakta P.Parthasarathi,Esq., L.M.S.,B.S.Sc.,(Mad)
L.R.C.P. & S.,(Edin.)D.T.M.(Lond.),D P.H.,(Camb.),
Director of Public Health in Mysore,
Bangalore.

Sir,

Re:- Treatment of tanks and water courses in and around Mysore City for anti=malarial purposes.

In enclosing herewith copy of letter No.L 12240/M1 92-45-2 dated 4th May 1946 received from the Revenue Secretary, on the above subject, I have the honour to state that a copy of the detailed estimate for Rs.1,40,000/- for the above work has been forwarded to you in this office No D2 C.85/44-45 dated 6th November 1945. The original copy of the report prepared by the Sanitary Engineer on 14th December 1942 to accompany the original estimate for Rs.49,800/-/- is herein enclosed for kind information.

This office is not aware of any of the items referred to in the estimate having been carried out by this Department or by the Health Department If any items have been worked out as pointed out in Para 1 of the Revenue Secretary's above letter, the same may kindly be intimated to him under advice to this office. The whole estimate for Rs.1,40,000/- may kindly be re-examined as desired by the Government and works required to be urgently carried out retained and estimated for.

After receipt of the estimate, duly revised or modified if necessary, further action will be taken to obtain sanction of Government therefor and allotment of funds to work up the urgent items of works referred to in Para 2 of the Revenue Secretary's above letter.

The estimate for Rs.1,40,000/- received back from Government, along with the original copy of the report prepared by the Sanitary Engineer is herewith enclosed for needful.

P.T.O.

The matter may kindly be treated as urgent.

I have the honour to be,
Sir,
Your most obedient servant,

(Sd) R Ramachandra Rao Bhombore

HRS/4.

Chairman.

D2 C85/44-45
23/5/46

Copy of the above is forwarded with compliments to the Revenue Secretary to Government of Mysore, Bangalore, for information with reference to his No L 12240/M1 92-45-2 dated 4th May 1946

HRS

Chairman

G R S App F G 3

GENERAL AND REVENUE SECRETARIAT

(*Continuation sheet draft form*)

(78)

13879/WE

The Chief Engineer
for Irrigation in
Tyre

Treatment of tanks and water courses in and around Tyre city, for anti-malaria purposes

Sir,

In inviting reference to this office memo No L-12242, dated 4-5-1946, on the above subject, I am directed to forward herewith a copy of letter No 13-M-1873 ~~on~~ dated 29-5-1946 received from the Director of Public Health and to request ~~you to~~ that the relative estimates may be reexamined and items which have been completed may be deleted and a revised estimate

pl Tyre

may be submitted to Govt for sanction, in consultation with the Director of Public Health and the Chairman, C.S.T. Board, Trichur

2) A copy of letter No D2 C-85/44-45 dated 21/5/46 received from the Chairman, C.S.T. Board, Trichur, addressed to the D.P.H is also enclosed

The question may be treated as very urgent and the above revised estimate may be submitted to Govt very early

TTS
pl Tyde

for Sec for

Revenue Dep
Memo No/13880/A1 & 11 6 46
Copy w.c to the Director of P. Health in Trichur for inform & necessary action with reference to his letter No B-M 1873 d 31-5-46

Copy w.c to Chairman C.S.T. Board, Trichur, for inform & necessary action with reference to his memo No D2-C-85 d 23/5/46

for Sec for Revenue

Urgent

(79)

No 3554/5

GEN & REV SECRETARIAT
27 JUNE 1946
L S G BRANCH

CHIEF ENGINEER
IRRIGATION & AGRI
25-6-46

GEN & REV SECRETARIAT
24
1 JULY 1946
L S G BRANCH

To

The Secretary to Government,
Revenue Department, Bangalore.

Sir,

Treatment of tanks and water courses in and around Mysore City for Antimalaria purposes

---

With reference to your letter No L 13879 dated the 11th June 1946 calling for the revised estimate for the above work, I have the honour to state that the original estimate has not been received in this office so far. It may kindly be caused to be sent to enable further action being taken thereon.

I have the honour to be
Sir,
Your most obedient servant,

Chief Engineer for Irrigation

SS.21/6

(80)

Immediate

No 200 & 47 Ele.

To The Chief Engineer for Irrigation in Mysore, Bl'ore

Subj. – Treatment of tanks and water courses in and around Mysore city, for Anti-malaria purposes

Sir,

With reference to your letter No 3554/S dated 25-6-46, on the above subject, I am directed to state that the original estimate for the work and other particulars, if any, required in this connection, may be kindly obtained from the Director of Public Health in Mysore, and the revised estimate called for in this office letter No C 13879 dated 11-6-46, may be submitted to Govt very early.

I have the honour
Your Obedt Servt

P T O

(81)

Memo No L201 cl 4 7 46

Copy w.c to the Director of Public Health in Lagos B'ham for information immediate return of the original estimate to the Chief Engineer for circulation

B-o
for Resident

GEN & REV SECRETARIAT
453
16 JULY 1946
L S G BRANCH.

(82)

B M 105/467
Sel(1)

Office of the Director of Public Health
in Mysore,
Bangalore, dated 8th July 1946

To

The Secretary to the Government of
His Highness the Maharaja of Mysore,
Revenue Department,
Bangalore

Sir,

Subject - Treatment of tanks and water
Courses in and around Mysore City
for anti-malaria purposes

I have the honour to enclose for the information of Government, a copy of letter addressed to the Chief Engineer for Irrigation in Mysore, Bangalore, forwarding the estimates referred to in memo No L 201, dated 4-7-1946

I have the honour to be,
sir,
Yourmost obedient Servant

DIRECTOR OF PUBLIC HEALTH

(84)

Office of the Director of Public Health
in Mysore,
Bangalore, dated 9th July 1946

To

The Chairman,
City Improvement Trust Board,
M Y S O R E

GEN & REV SECRETARIAT
452
16 JUL 1946
S G BRANCH

S i r,

With reference to your letter No D2 C 85/44-45, dated 21st/23rd May 1946, I have the honour to state, that I am not aware of any one item or part thereof of the works provided for in the estimate for rupees 1,40,000/- having been already done, either by City Improvement Trust Board or by the Health Department. I have, therefore, as required by Government forwarded the estimates as revised in original to the Chief Engineer for Irrigation in Mysore, Bangalore, for necessary further action in the matter

I have etc ,

BU 103/46-7

Sd/- P Parthasarathy,
Director of Public Health

Copy forwarded w/e to the Secretary to Government, Revenue Department, Bangalore, for favour of information

J Chandrashekaraya
DIRECTOR OF PUBLIC HEALTH

the

relin

ka

No. 237/5

(85)

Office of the Chief Engineer
for Irrigation,
Bangalore, dated 30 July 1946

To

The Secretary to Government,
Revenue Department,
Bangalore

GEN & REV SECRETARIAT
1023
8 AUG 1946
BRANCH

Sir,

Treatment of tanks and water courses in and around Mysore City for Anti-malaria purposes

- - -

With reference to your letter No L 200 dated 4/7-1946, on the above subject, I have the honour to state that the revised estimate for the above work will be sent to Government for orders on its receipt in this office Needful action to obtain the same is being taken

I have the honour to be
Sir,
Your most obedient servant,

CHIEF ENGINEER FOR IRRIGATION

VVR

No. 405/S 10/8/46 OFFICE

To

GEN & REV SECRETARIAT 1296 17 AUG 1946 L.S.G. BRANCH

The Secretary to Government,
Revenue Department, Bangalore

Sir,

Treatment of tanks and water courses in and around Mysore City, for anti-malaria purposes

With reference to correspondence ending with this office letter No 237/S dated 30-7-46 on the above subject, I have the honour to state that the estimates and plans for the work have just been received in this office from the Director of Public Health in Mysore, Bangalore

I am inspecting the locality on 14-8-46 and shall furnish my remarks thereafter

I have the honour to be,
Sir,
Your most obedient servant,

Arc 10-8

Chief Engineer for Irrigation

Letter No 104/46 dated 9-7-46 from the Director of Public Health in Mysore, Bangalore, to the Chief Engineer for Irrigation in Mysore, Bangalore

---

Subject - Treatment of tanks and water courses in and around Mysore City, for anti-malaria purposes.

--

With reference to letter No E 201, dated 4-7-1946, from the Secretary to Government, Revenue Department, I have the honour to enclose for favour of necessary action, a set of seven estimates with regard to treatment of tanks and water courses in and around Mysore City for anti-malarial purposes

---

"C O P Y"

J Chandrashekarappa
DIRECTOR OF PUBLIC
HEALTH i/c

(87)

No. 573/S
Enc.

27

Office of the Chief Engineer
for Irrigation in Mysore,
Bangalore, dated 21 Aug.1946.

GEN. & REV. SECRETARIAT
1749
2 SEP 1946
L S G Br. NOH.

To

The Secretary to Government,
Revenue Department,
B a n g a l o r e.

Sir,

Treatment of tanks and water
courses in and around Mysore
City for anti-malaria purposes

With reference to my letter No 405/S dated 10-8-1946 - regarding the above, I have the honour to state that in connection with the proposals made for dealing with certain areas in Mysore - City as an anti-malaria measure, the Chairman, Mysore City Improvement Trust Board, the Chief Engineer for Roads and Buildings, and myself jointly inspected the several localities The Health Officer of the Mysore City Municipality was also present

The estimates amounting to Rs.1,11,525/- provided for

(1) Sub-soil drains in Halladakere area,
(2) Sub-soil drain behind the Karanjikere,
(3) Sub-soil drains in Doddakere tank bed,
(4) Breaching of Goblikatte, etc ,
(5) Sub-soil drains behind the Kukkanahallikere area,

(1) The first area inspected, viz , the Halladakere region of - the old City, is no doubt saturated and the sub-soil water level is high We consider that proposals made for sub-soil drainage in this area may be given effect to It is also suggested as an experimental measure to have an open well and pump out water, utilising it for - gardens and parks If this is successful, this can be extended.

(2) Karanji Tank - It was explained that the treatment of this - area was intended to give protection to the Body-Guard residential - quarters and other inhabited areas in the vicinity. The Sub-soil drain proposed behind the bund is only to get rid of the seepage to some -

some extent and the main source of breeding of mosquitoes, the tank, is untouched We are not in favour of the drastic remedy of breaching the tank as it is used for providing water for certain residential areas It was suggested that as an alternative the edges of the water spread be always kept clean by periodical removal of rank vegetation and the breeding of mosquitoes be stopped by regular spraying of either Paris Green or Pyrethrum solution The feeder channel leading to this tank has got to be dealt with i n such a manner that in the ordinary seasons it should not give scope for small stagnant pools, which are fruitful breeding places of - mosquitoes This can be best done by the present central earthern drain being suitably graded and properly lined

(3) Proposals made for the breaching of the Goblikere and - retaining only small area for a pond and other measures in this section may be given effect to.

(4) In regard to Doddakere area, we feel that the sub-soil drain would not be effective It is very necessary that the whole bed of the tank should be properly levelled and this can best be - done by using Bull Dozers and graders By means of lateral and - longitudinal drains the surface drainage can be effectively dealt with, no scope being afforded for the formation of puddles etc

It is also felt that the present collecting drain in the southern end leading off into the waste weir draft channel has not got sufficient gradient as a consequence of which, there is undesirable stagnation of water right through.

The Trust Board Engineer has been asked to examine by levels whether the lead off drain could not be connected with the sluice in the main bund In case of necessity, the sluice might be lowered by a few feet to provide a good fall which is very essential to drain away the bed of the tank completely As an anti-malaria measure, it seems to be absolutely necessary that the garden behind the Doddakere should be fully acquired and kept clear of the breeding places, particularly the extent to the North of the proposed continuation of the

of the Vani Vilas Road to meet the Doddakere tank bund The Scheme to continue this Road across the tank bed making a gap in the bund will further assist in the draining of this tank bed And pending such - action it is essential that the valley portion should be kept clear of stagnant pools

As this is a very urgent matter, the Trust Board Engineer has been asked to prepare immediately an estimate incorporating the above suggestions

The area behind the Kukkanahalli tank commencing from the rear of the bund up to Jayanagar cannot be satisfactorily dealt with by simple sub-soil drains and the Chairman, Trust Board, Mysore, was also of the view that it need not be mixed up with the present proposal and that it may be dealt with as an independent proposition altogether. This would necessitate also dealing with the Kukkanahalli tank bed as well

The Chairman, City Improvement Trust Board, is requested to have estimates prepared on the lines suggested above The Director of Public Health will be consulted after these estimates are prepared.

I have the honour to be
S i r,
Your most obedient servant,

M Narasimha

ksr. 26th.

CHIEF ENGINEER FOR IRRIGATION

Immediate

The Chairman, C.I.T. Board
Mysore

Treatment of tanks and water courses in and around Mysore city for anti-malaria purposes

Sir

With reference to the correspondence ending with this office memo no L 13881 dated 11-6-46, on the above subject, I am directed to state that the Chief Engr for Irrigation has since intimated that he has, after inspection in company with the C.I.T. engineers, issued necessary instructions to the Trust Board Engr, Mysore city, to prepare immediately the estimates

(101)

on the lines suggested by him

I am to request that the concerned estimates may be arranged to be forwarded to the Chief Engr for scrutiny, without any delay as this ~~is an~~ important question which has been pending since Nov, 1941 ~~and~~ has to be disposed of without any further delay

I have the
honour
Sd/-
Secretary

Memo no L 3260 & 5946
copy refer to the C-E for scrutiny w.r.to his letter no 5787/S dt 31/8/42

Ans
for necessary

(112)

(102)

5308 8 30 10 46

To The Chairman, C & T Board

Mysore

Treatment of tanks and water courses in and around Mysore city — for anti-malaria purposes

Sir,

In inviting reference to this office letter No. L 2257 dated 5-9-46 on the above subject, I am directed to enquire whether the estimate in question has since been sent to the Chief Engr for sanction for scrutiny and ——

Return A very (183) early reply

We have the
for Secretary

Memo No L 5309 dd 30 10 46

Copy w-c to CE for verse for infmn,

with the request that the estimates in question if they have been returned to Chancellor of Exchequer should be submitted to Exch very early

MBO
for Secretary

(104)

No. D_3 C 105/46-47

Office of the Chairman,
City Improvement Trust Board,
Mysore, dated 4th November 1946

4/11/46

6 NOV 1946
L 3380
L S G BRANCH
GEN & REV SECRETARIAT

FROM N MADHAVA RAO, Esq., B A,
CHAIRMAN, CITY IMPROVEMENT TRUST BOARD,
MYSORE

J B Mallaradhya, Esq, M A,
SECRETARY TO THE GOVERNMENT OF
HIS HIGHNESS THE MAHARAJA OF MYSORE,
Revenue Department, BANGALORE

SIR,

Subject:- Treatment of tanks & water course in and around Mysore City

---

With reference to your No L 5308 dated 30th October 1946 enquiring whether the estimates in question have since been sent to the Chief Engineer for Irrigation, I have the honour to inform you that the concerned estimates for Doddakere Tank as suggested by the Chief Engineer were prepared and sent to him in this Office No D_3 C 105/46-47 dated 26th October 1946 for necessary action

I have the honour to be,
Sir,
Your most obedient servant,

Chairman I/c

HRS

(112)

Revised copy attached for

Immediate - (105)

No L 5816 dt 12-11-46

Subj - Treatment of tanks and water courses in and around Lyallpur City.

Dear Sir,

With reference to the correspondence ending with your Office memo No L 530 dated 30-10-46 I am desired to state that the Chairman, C S-T Board Lyallpur has since intimated that the concerned estimates for the Doddakeere tank were sent to you on 26-10-46

I am ~~der~~ to request that the

[illegible]

[illegible]

[illegible]

[illegible]

[illegible]

(112)

(107)

No. 1000/S

OFFICE OF THE CHIEF ENGINEER FOR IRRIGATION BANGALORE

21/11

GEN & REV SECRETARIAT 1932 22 NOV 1946 L S G BRANCH.

To

The Secretary to Government,
Revenue Department, Bangalore

Sir,

Re Treatment of tanks and water courses in and around Mysore City - Draining of Doddakere Tank bed

---

With reference to your Memo No L 5309 dated 30-10-1946 and subsequent D O letter No L 5816 dated 12-11-46 regarding the above, I have the honour to state that the estimate amounting to Rs 69,000/- received from the Chairman, City Improvement Trust Board, Mysore, has been forwarded to the Chief Engineer for Roads & Buildings in Mysore, Bangalore, for favour of remarks

2 Further action will be taken on its receipt

I have the honour to be,
Sir,
Your most obedient servant,

Chief Engineer for Irrigation

Arc 16-11

Immediate (112)

REV SECRETARIAT 29

(108) Immediate

80 86 07 30 11 46 3

To

The Chief Engineer for
Irrigation in Mysore

Treatment of tanks and water courses in and around Mysore city

Sir,

With reference to the correspondence ending with your letter No 1000/3 dated 21-11-46 on the above subject, I am directed to state that the relative estimates for the municipally-worked works called for, in this office letter No L 12240/ML 92452 dated 4-4-46, may be

(109)

Kindly arranged to be submitted to Govt immediately.

X

1) Kukkarahalli tank
2) Doddakere
3) Hallada Kere Drainage Scheme

Shave Cu
for
For Revenue

Memo No. L 8087 dt 30-11-46

Copy we to the Chairman, C.S.

To Board, Mysore, for information. also,
Memo L. 8088 & 30-11-46 for
Copy we to the Chief Engr for Roads & Buildings, with a request that the estimate for the proposed Doddakere tank may be kindly returned with his remarks to the C.S. for orders immediately

for Revenue

Immediate (112)

(140)

REN & REV SECRETARIAT 5527 15 JAN 1947 G. BRANCH

No. 5483

GOVERNMENT OF MYSORE

OFFICE OF the Chief Engineer for Roads and Buildings in Mysore, Bangalore.

Date 10-1-47

To

The Secretary to Government,

Revenue Department, Bangalore.

Sir, Treatment of tanks and water courses in around Mysore City - Draining of Doddakere tank bed.

With reference to your memo No.L.8088 dated 30-11-46 regarding the estimate amounting to Rs 69,000/- for the above work, I have the honour to forward herewith, for information, a copy of this office letter No 5188 dated 4-1-1947 addressed to the Chairman, City Improvement Trust Board, Mysore, requesting for certain particulars being furnished. After these particulars are received the estimate will be scrutinised.

I have the honour to be
Sir,
Your most obedient servant,

Chief Engineer for Roads
and Buildings.

K.G

(112)

Immediate

L 10374 D/22/47

To

The Chairman, C.S.T. Board,
Mysore

Treatment of tanks and water courses in and around Mysore city

Sir,

In inviting reference to letter No. 5188, dated 4-1-1947, from the Chief Engineer for Roads & Buildings in Mysore, to your address, I am directed to enquire whether the particulars referred to therein have

since been furnished by you to that
Office if not arrangements may
kindly be made to furnish them
immediately as this question has been pending
for a long time & has to be disposed of
without any further delay & have the

For Secretary

Memo No L 10375 d D 22-1-47

Copy we to the Chief Engineer for
Roads & Buildings for information with reference
to his letter No 5483 D 10-1-47

For Secretary

No. D_3.C-105/45-46

Office of the Chairman,
City Improvement Trust Board,

Mysore, dated 29th January 1947

FROM R RAMACHANDRA RAO BHOMBORE, Esq, B A,
CHAIRMAN, CITY IMPROVEMENT TRUST BOARD,
MYSORE

NEW SURVEY SECRETARIATE
11 FEB 1947

TO J B MALLARADHYA, Esq, M A,
SECRETARY TO THE GOVERNMENT OF
HIS HIGHNESS THE MAHARAJA OF MYSORE,
Revenue Department, BANGALORE

SIR,

Re Treatment of tanks and water courses in & around Mysore City

---

With reference to your letter No L 10374 dated 22-1-47 enquiring whether the particulars required by the Chief Engineer Roads and Buildings in his letter No 5188 dated 4-1-1947 on the above subject have been furnished by me to that Officer, I have the honour to state that all the particulars required by him have been given to him in person on the 21st instant alone

REVENUE SECRETARIATE
No
Date
GOVERNMENT OF MYSORE

I have the honour to be,
Sir,
Your most obedient servant,

Chairman

HRS

(115) d 11475

20/2/47

To.

The Chief Engineer for Roads and Buildings in Mysore

Subject:- Treatment of tanks and water courses in and around Mysore City

Sir,

In continuation of this office memo No d 10375 dated 22-1-47 on the above subject, I am directed to state that the Chairman C & T Board, Mysore, has, since reviewed the all the particulars received by you have been furnished to you in

(116)

Person on 21-1-1949

I am to request that the relative estimates called for in this office letter No L 12240 AHL 92-45=2, dated 4-4-49 and subsequent reminder No L 8056 dated 30-11-49 may be kindly submitted to Qat immediately as this urgent and important question is pending for a very long time

Memo No L 11476 dt 20/2-/49 Copy we to Chairman, C.S.I. Board, Mysore, for information

To Reader

I have to for information

To Reader

(111)

Letter No.5188 dated 4-1-1947 from the Chief Engineer for Roads and Buildings in Mysore, Bangalore, to the Chairman, City Improvement Trust Board, Bangalore.

Treatment of tanks and water courses in and around Mysore City
Draining of Doddakere tank bed.

With reference to your letter No.D.3.C 105/46-47 dated 23-10-1946 addressed to the Chief Engineer for Irrigation forwarding an estimate amounting to Rs.69,000/- for the above work, I have the honour to request you to be so good as to furnish the following particulars -

i. Sections of lateral and longitudinal drain.
ii. Run off into the tank and discharge calculations of the drains.
iii. Details of the protective works.
iv. Topo sheet extract showing the position of tank, lands to be acquired etc ,
v. Data sheets for the rates claimed in excess of the schedule rates

---

" Copy "

Chief Engineer for Roads
and Buildings.

K.G

G R

UBS

Me 38-46-118 (117)

No 1916/S

Office of the Chief Engineer
for Irrigation in Mysore,
Bangalore, Dated, 15th March 1947

GEN & REV SECRETARIAT
7679
13 MAR 1947
L S G BRANCH

No

The Secretary to Government,
Revenue Department,
Bangalore

Sir,

Treatment of tanks and water courses in and around Mysore - Draining of Doddakere Tank bed

---

In continuation of No 5483 dated the 10th January 1947 from the Chief Engineer for Roads & Buildings, I have the honour to forward herewith an estimate for Rs 79,100/- for draining of Doddakere Tank bed for taking further action

The area was inspected by me and the Chief Engineer for Roads & Buildings on the 15th January 1947 Detailed instructions were given to the Trust Board Engineer at Mysore to modify the estimate already prepared with a view to eliminate the stagnation of water in pools in the bed of the tank after rains

The proposals now got up by the Trust Board Engineer have been scrutinised in this office for Rs 79,100/- The proposal is for grading the tank bed suitably after removal of silt and for canalising the area with rough stone channels with 1 2 4 cement - - concrete silk pattern inverts of suitable sizes Adequate cross fall of 3" in 10' is given in the channel from the side to the centre for proper drainage All the other necessary provisions such as lowering the draft channel and provision of weirs and - bridges for the use of pedestrains and cattle are all made in the estimate

After these capital works are executed, it is very necessar to maintain the channels free from silt and drainage by cattle and other sources This will have to be arranged for by the staff of the Municipality

I recommend the proposals now made for sanction as one of the antimalarial measures and to keep the tank bed dry.

I have the honour to be
Sir,
Your most obedient servant,

CHIEF ENGINEER FOR IRRIGATION

SS 11/3

G R S App F VI—G 2]

SUBJECT

(119)

Diary No of letter replied to

General and Revenue Secretariat

( )

the 194

Date of issue 26/5/47 194

Signed by G R Rao

May this be—

(i) printed ?

(ii) treated as a Standing Order ?

(iii) published in the Gazette English Part ?

(iv) translated ?

(v) placed at the disposal of the Press ?

(vi) published in the Gazette Kannada Part ?

Section Ml

File No 38-46

Serial No 119

Proceedings of the Government of His Highness the Maharaja of Mysore

Read — Letter No L1 22 40/Ml 92-45-2 dt 4-5-46 addressed to the Chairman, C & T Board - Mysore, submitting representations for the treatment of tanks and water courses in and around Mysore city — Read 2 letters correspondence ending with letter No D3 C 105/45-46 dated 24-1-47 from the Chairman, C & T Board - Mysore - ~~forwarding~~ ~~for report~~ forwarding proposals in regards to the treatment of tanks and water courses in and around Mysore city 3) Correspondence ending with letter No 1916/J dated 15-3-47 from the Chief Engineer for Irrigation forwarding for sanction an estimate for Rs 79,100- for the draining of the Doddakere tank in Mysore of h 16393-8 Ml 38-46-119 city order No dt 26/5/47.

The question of the

treatment of tanks and water courses in and around the Mysore city for anti-malaria purposes has been under examination in the departments of public health and public works and the Mysore city improvement Trust board for a long time

In February 1926 the Director of Public Health submitted for sanction an estimate for Rs. 1,40,000 for the execution of the minimally-priced works to bring down malaria in the city

On finding that some of the items provided in the above estimate had already been attended to by the Health Department or by the Trust Board, and that some of the items required immediate execution, ~~on the letter dated 4-2-26, send above~~ the following instructions

List of Enclosures

1) Subsoil drainage in the near of the Kukkarahalli tank
2) Shravanee Feeder channel to Kanangi Kere
3) Subsoil drainage to the Lucerene gardens
4) Subsoil drainage to the near of the Kanangi Kere
5) Subsoil drainage to the Gobli Kere
6) Subsoil drainage to the Doddakere
7) Subsoil drainage to the Hallada Kere

~~Copied by~~
~~Examined by~~

were issued ~~by the~~ chairman of the Trust Board:

1) ~~that~~ priority be given to the Kukkarahalli and Doddakere tanks and the Hallada kere drainage scheme which might be taken up first and completed quickly

2) the relative estimates may be examined and items which had been completed must be deleted.

and 3) the works may be carried out by the Mysore C & T Board with the advice of the Sanitary Engineer

On August 1965 the Chairman, C & T Board - Mysore - the Chief Engineer for Irrigation and the Chief Engineer for Roads and Buildings, ~~and the Health Officer - etc~~ ~~were holding~~

Rec'd a joint inspection of the several areas and discussed the ~~several~~ relative advantages of the proposed measures, ~~[illegible]~~ it was then decided ~~that~~ to have the estimates prepared for the several works on the lines decided at the joint inspection

The Chief Engineer for Irrigation has accordingly submitted for sanction an estimate of Rs 29,100- for draining the Doddalakere tank bed, in Mysore. The estimate provides the grading of the tank bed suitably, the removal of the silt in the tank bed, the canalising of the area with rough stone channels, etc.

Government are pleased to sanction the above estimate for Rs 29,100-, the cost being met out of the provision of Rs 82,000 made under "Anti-malaria measures in Mysore city" in the current year's State Budget.

From
Revenue Department

The Chairman C & T Board - Mysore (W.R.)
" Chief Eng for Irrigation
" " for Roads & Buildings
" President - City Mun. of Mysore
" Director of Public Health
" Comptroller to Gov.

(123)

PROCEEDINGS OF THE GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

Read:

Letter No. L. 12040/Ml. 92-45-2 dated 4.5.46 addressed to the Chairman, City Improvement Trust Board, Mysore issuing instructions regarding the treatment of tanks and water courses in and around Mysore City.

2. Correspondence ending with letter D3.C. 105/45-46 dated 24th January 1947 from the Chairman, City Improvement Trust Board, Mysore forwarding proposals in regard to the treatment of tanks and water courses in and around Mysore City.

3. Correspondence ending with letter No. 1916/3 dated 15.3.47 from the Chief Engineer for Irrigation forwarding for sanction an estimate for Rs.79,100/- for the draining of the Doddakere tank in Mysore City.

Order No. L 16393-8 ML 38-46-119

Bangalore, Dated 26th May 1947.

The question of the treatment of tanks and water courses in and around the Mysore City for anti-malaria purposes has been under examination in the Departments of Public Health and Public Works and the Mysore City Improvement Trust Board for a long time.

In Febtuary 1946 the Director of Public Health submitted for sanction an estimate for Rs. 1,40,000 for the execution of the marginally noted works to bring down Malaria in the City.

1. Subsoil drainage in the rear of the Kukkanahalli tank.
2. Increasing Feeder Channel to Karangikere.
3. Subsoil drainage to the Lucerena gardens.
4. Subsoil drainage to the rear of the Karangikere.
5. Subsoil drainage to the Goblikere.
6. Subsoil drainage to the Doddakere.
7. Subsoil drainage to the Halladakere.

On finding that some of the items provided in the above estimate had already been attended to by the Health Department or by the Trust Board, and that some of the items required immediate execution the following instructions were issued to the Chairman of the Trust Board.

1. priority be given to the Kukkanahalli and Doddakere tanks and the Yelladakere drainage Scheme which might be taken up first and completed quickly.

2. the relative estimates may be examined and items which had been completed might be deleted.

3. the works may be carried out by the Mysore City Improvement Trust Board with the advice of the Sanitary Engineer.

In August 1946, the Chairman, City Improvement Trust Board, Mysore the Chief Engineer for Irrigation and the Chief Engineer for Roads and Bldg held a joint inspection of the several areas and discussed the relative advantages of the proposed measures. It was then decided to have the estimates prepared for the several works on the lines decided at the joint inspection.

The Chief Engineer for Irrigation has accordingly submitted for sanction an estimate for Rs.79,100/- for draining the Doddakere tank bed, in Mysore. The estimate provides for the grading of the tank bed suitably, the removal of silt in the tank bed, the canalising of the area with rough stone channels etc.

Government are pleased to sanction the above estimate for ~~Rs.79,100~~ Rs. 79,100 the cost being met out of the provision of Rs.62,000 made under "Antimalaria measures in Mysore City" in the current year's State Budget.

For Secretary to Government,
~~Budget~~ Revenue Department.

The Chairman, City Improvement Trust Board, Mysore ~~xxxxxxxxxxxx~~ (with records,
The Chief Engineer for Irrigation;
The Chief Engineer for Roads & Buildings;
The President, City Municipal Council, Mysore;
Director of Public Health in Mysore, Bangalore;
The Controller to Government of Mysore, Bangalore.

98760
18000